

MIRADA

PHASE 1 MASS GRADING PLAN

Prepared For:
CRCG TWO LP
C/O METRO DEVELOPMENT GROUP, LLC
 2502 NORTH ROCKY POINT DRIVE SUITE 1050
 TAMPA, FL 33607
 Phone: (813) 288-8078

5806-B Breckenridge Parkway
 Tampa, Florida 33610
 Office: 813-253-5311
 Fax: 813-464-7629
 www.HeidtDesign.com




HEIDT DESIGN
 Civil Engineering • Planning & GIS
 Transportation Engineering
 Ecological Services • Landscape Architecture


Engineering Business Certificate of Authorization No. 28782
 Landscape Architecture Certificate of Authorization No. LC26000405

CONSTRUCTION PLAN

SECTIONS 10, 11, 14, & 15 TOWNSHIP 25 SOUTH, RANGE 20 EAST
 PASCO COUNTY, FLORIDA



LOCATION MAP
(NOT TO SCALE)



SITE MAP
(NOT TO SCALE)

LEGAL DESCRIPTION

The southern 1,000 feet of the eastern 450 feet of the southeast quarter of Section 10, Township 25 South, Range 20 East; and the western 215 feet of the southern 1,000 feet of the southeast quarter of Section 11, Township 25 South, Range 20 East; and the southern 1,000 feet of the southwest quarter of said Section 11; and that portion of the western 215 feet of the northeast quarter of Section 14, Township 25 South, Range 20 East lying west of the eastern right-of-way of Curley Road; and the northwest quarter of said Section 14; and the northern 149 feet of the southwest quarter of the southwest quarter of said Section 14; and the northern 328 feet of the northeast quarter of the southwest quarter of said Section 14; and the eastern 1,200 feet of the southeast quarter of the northeast quarter of Section 15, Township 25 South, Range 20 East; and the eastern 1,200 feet of the northeast quarter of the southeast quarter of said Section 15; less and except the right-of-way of Curley Road pursuant to O.R. Book 54, Page 83, all lying in Pasco County, Florida.

OWNER/DEVELOPER:
 CRCG TWO LP
 C/O METRO DEVELOPMENT GROUP, LLC
 2502 NORTH ROCKY POINT DRIVE
 SUITE 1050
 TAMPA, FL 33607
 (813) 288-8078
 ATTN: MIKE LAWSON,
 DIRECTOR OF DEVELOPMENT

GEOTECHNICAL ENGINEER:
 FAULKNER ENGINEERING SERVICES, INC.
 2734 CAUSEWAY CENTER DRIVE
 TAMPA, FL 33619

SURVEYOR:
 DC JOHNSON & ASSOCIATES
 11911 SOUTH CURLEY STREET
 SAN ANTONIO, FL 33576
 (352) 588-2768

CIVIL ENGINEER:
 HEIDT DESIGN, LLC
 EDWIN J. ROGERS P.E.
 5806-B BRECKENRIDGE PARKWAY
 TAMPA, FLORIDA 33610
 (813) 253-5311

THESE PLANS HAVE BEEN PREPARED IN ACCORDANCE WITH THE MANUAL OF UNIFORM MINIMUM STANDARDS FOR DESIGN, CONSTRUCTION AND MAINTENANCE FOR STREETS AND HIGHWAYS, STATE OF FLORIDA IN EFFECT AT THE TIME OF PASCO COUNTY APPROVAL, AND ARE IN COMPLIANCE WITH THE STANDARDS THEREIN EXCEPT AS NOTED ON THE PLANS. ANY DEVIATIONS NOTED ON THE PLANS SUBSTANTIALLY COMPLY WITH THE INTENT OF THE STANDARDS.

Sheet List Table	
Sheet Number	Sheet Title
C-100	COVER
C-101	GENERAL NOTES
C-102	AERIAL SITE PLAN
C-200	OVERALL MASS GRADING PLAN
C-201	KEY MAP
C-202	MASS GRADING PLAN
C-203	MASS GRADING PLAN
C-204	MASS GRADING PLAN
C-205	MASS GRADING PLAN
C-206	MASS GRADING PLAN
C-207	MASS GRADING PLAN
C-208	STORM STRUCTURE DATA
C-209	MASS GRADING DETAILS
C-210	MASS GRADING DETAILS
C-231	FLOODPLAIN MITIGATION & POND DETAILS
C-232	FLOODPLAIN MITIGATION & POND DETAILS
C-900	PRE-DEVELOPMENT BASIN MAP
C-901	POST-DEVELOPMENT BASIN MAP
C-902	CSWMP
C-903	CSWMP
L-100	TREE REPLACEMENT CHARTS
L-101	TREE REMOVAL & REPLACEMENT PLAN
L-102	TREE REMOVAL & REPLACEMENT PLAN
L-103	TREE REMOVAL & REPLACEMENT PLAN
L-104	TREE REMOVAL & REPLACEMENT PLAN
L-105	TREE REMOVAL & REPLACEMENT PLAN
L-106	TREE REMOVAL & REPLACEMENT PLAN

PASCO COUNTY SUBMITTAL DATE:
 DECEMBER 15, 2014

MIRADA
 PHASE 1 MASS GRADING PLAN

METRO DEVELOPMENT GROUP, LLC

DATE	DESCRIPTION	DATE	DESCRIPTION
12/15/2014	REVIEW SUBMITTAL		



ELEVATIONS BASED ON:
 NORTH AMERICAN VERTICAL DATUM
 CONVERSION: NAVD 88 TO NGVD 29 = +0.85

PERMIT / FILE NUMBERS	
SWFWMD	
WATER DEP	
SEWER DEP	
TAX PARCEL I.D. Nos.	

FLORIDA PROFESSIONAL ENGINEER	FILE:	COVER
EDWIN J. ROGERS DATE: _____ REGISTRATION NO. 50082	PROJECT NO:	CRP CR 1024
	GRADING & DRAINAGE	
	DESIGN BY:	RUSSUM
	DRAWN BY:	FRANCIS
	UTILITIES	
	DESIGN BY:	WS DESIGN
	DRAWN BY:	WS DRAWN
	COVER	
	C-100	

	1	2	3	4	5	6
E	<p>STORM WATER POLLUTION PREVENTION PLAN</p> <p>Contained on these plans and within the following notes is a storm water pollution prevention plan (swppp) which has been developed by Heidt Design, LLC in accordance with the Florida Department of Environmental Protection's (FDEP) "National Pollutant Discharge Elimination System" (NPDES) generic permit for stormwater discharge from large and small construction activities.</p> <p>The following entities are identified as team members of "SWPPP": Heidt Design, LLC, the developer as identified in the title box of these plans, and the site contractor and his sub-contractors. Each team member has specific responsibilities and obligations. In general, all team members, with regard to their involvement and responsibilities on the project, are to implement all necessary storm water management controls to assure compliance with the NPDES generic permit for storm water discharges from construction activities, the Southwest Florida Water Management District Permit, the applicable local governing agency (i.e. Pasco County) and the guidelines listed in the SWPPP. The duties and responsibilities of the team members as they pertain to the SWPPP are as follows:</p> <p>HEIDT DESIGN, LLC:</p> <p>A. Develop SWPPP including, but not limited to, retention/detention ponds, control structures, erosion control methods and locations and stabilization criteria. This design is included within these construction plans and the following notes and instructions.</p> <p>B. Submit and obtain the necessary design related storm water permits from the Florida Department of Environmental Protection, the Southwest Florida Water Management District and other applicable governmental bodies.</p> <p>C. Upon notification by the developer of his intent to commence construction, submit a copy of intent to the FDEP on behalf of the developer and copy the contractor including SWPPP certification and notice of the permit.</p> <p>D. Submit to SWFWMD and the operator of the municipal separate storm water system, if applicable, a letter of construction commencement.</p> <p>E. Complete and submit a notice of termination and certification for developer. The NOT's shall be submitted no more than 30 days after:</p> <p>(a) Completion of the project and final stabilization of the site or</p> <p>(b) When responsibility for the site has ended. Final stabilization as defined by EPA is when all soil disturbing activities at the site have been completed and a uniform (e.g. evenly distributed, without large bare areas) perennial vegetative cover with a density of 70% of the native background vegetative cover for the area has been established on all upland areas and areas not covered by permanent structures. As an alternative, equivalent permanent stabilization measures (such as straw, gabions, or geotextiles) may be employed. The client shall notify Heidt Design, LLC when one of these criteria has been met.</p> <p>CONTRACTOR:</p> <p>A. Sign and return to Heidt a contractor certification form certifying your understanding of and willingness to comply with the Storm Water Pollution Prevention Plan no later than 48 hours prior to commencement of construction. The site sub-contractor shall certify to Heidt Design, LLC that the contractor that they understand and shall comply with the NPDES Permit and SWPPP. A record of these certifications shall be maintained by the contractor on site.</p> <p>B. During construction, assure compliance with the designed Storm Water Pollution Prevention plans prepared by Heidt Design, LLC and the NPDES Generic Permit for storm water discharges from large and small construction activities.</p> <p>C. Maintain a copy of the construction plans, which include the Storm Water Pollution Prevention Plan, the NOI, and all inspection reports and certifications on site.</p> <p>D. Undertake all reasonable Best Management Practices (BMP's) to assure that silted or otherwise polluted storm water is not allowed to discharge from the site during all phases of construction. Stabilization BMP's that may be used include:</p> <p>Temporary or permanent seeding, mulching, geotextiles, sodding, vegetative buffer strips, protection of trees and preservation of mature vegetation. Structural erosion and sediment control BMP's that may be used include: straw bale dikes, silt fences, earth dikes, brush barriers, drainage swales, check dams, subsurface drain, pipe slope drain, level spreaders, storm drain inlet protection, outlet protection, sediment traps, and temporary sediment basins. Detention ponds may also be used as temporary sediment basins. Additional BMP's that may need to be implemented include: providing protected storage areas for chemicals, paints, solvents, fertilizers, and other potentially toxic materials. Providing waste receptacles at convenient locations and providing regular collection of wastes, including building material wastes. Minimizing off-site tracking of sediments. Making adequate preparations, including training and equipment to contain spills of oil and hazardous materials. Complying with applicable state or local waste disposal, sanitary sewer or septic system regulations and the use of appropriate pollution prevention measures for allowable non-storm water components of discharge.</p> <p>E. Notify Heidt Design, LLC and the developer in writing of any non-storm water pollution sources which are being stored, or otherwise used during the construction of the project, i.e., fertilizers, fuels, pesticides, other chemicals. This notification should be accompanied with the contractor's design and methods to prevent pollution run-off from these sources.</p> <p>F. Develop a maintenance and inspection plan which includes, but is not limited to the following:</p> <p>(a) The specific areas to be inspected and maintained that includes all the disturbed areas and material storage areas of the site.</p> <p>(b) The erosion and sediment controls identified in the swppp to be maintained and inspected and those additional controls that the contractor deems necessary.</p> <p>(c) Maintenance procedures.</p> <p>(d) The procedure to follow if additional work is required or whom to call.</p> <p>(e) Inspections and maintenance tasks.</p> <p>(f) The personnel assigned to each task.</p> <p>The following shall be inspected a minimum of once a week or within 24 hours after 0.50 inches of rainfall:</p> <p>Stabilization measures (once a month if fully stabilized).</p> <p>Structural controls.</p> <p>Discharge points.</p> <p>Construction entrances and exits.</p> <p>Areas used for storage of exposed materials.</p> <p>An inspection form shall be completed for each inspection. Any permit violations should be noted and corrective measures shall be taken no later than 7 days after the inspection occurred. If revisions to the SWPPP are needed, a report form for changes in the SWPPP shall be completed and a copy sent to Heidt Design, LLC the original shall be kept on-site as documentation of the change. If the inspection passes, a certification that the facility is in compliance with the SWPPP and the NPDES Permit must be signed by a duly authorized representative of the principal executive officer of the operator of the SWPPP with one of the following qualifications:</p> <ol style="list-style-type: none"> Has successfully completed the Florida Stormwater, Erosion and Sediment Control Inspector Training Program. Successfully completed a similar training program. Has enough practical on the job training to be qualified to perform the inspections. Retain inspection reports and certifications for at least three years. <p>G. Site stabilization measures shall be initiated as soon as practical but in no case more than 7 days, in portions of the site where construction activities have temporarily or permanently ceased.</p> <p>H. Releases in excess of reportable quantities.</p> <ol style="list-style-type: none"> The discharge of hazardous substances (as in the stormwater discharge) from a facility or activity shall be prevented or minimized in accordance with the applicable Stormwater Pollution Prevention Plan for the facility or activity. This permit does not relieve the operator of the reporting requirements of 40 cfr part 117 and 40 cfr part 302. Where a release containing a hazardous substance in an amount equal to or in excess of a reporting quantity established under either 40 cfr 117 or 40 cfr 302, occurs during a 24-hour period: The operator is required to notify the State Warning Point (800-210-0519 or 850-413-9911) as soon as she or she has knowledge of the discharge; The operator shall submit within 14 calendar days of knowledge of the release a written description of the release (including the type and estimate of the amount of material released), the date that such release occurred, the circumstances leading to the release, and remedial steps to be taken, to the Florida Department of Environmental Protection, NPDES Stormwater Section, Mail Station 2500, 2600 Blair Stone Road, Tallahassee, Florida 32309-2400; and The Stormwater Pollution Prevention Plan required under part V of this permit must be modified within 14 calendar days of knowledge of the release to provide a description of the release, the circumstances leading to the release, and the date of the release. In addition, the plan must be reviewed to identify measures to prevent the recurrence of such releases and to respond to such releases, and the plan must be modified where appropriate. <p>2. This permit does not authorize the discharge of hazardous substances or oil resulting from an on-site spill.</p>					
	D	<p>GENERAL EROSION AND TURBIDITY CONTROL NOTES</p> <ol style="list-style-type: none"> The Site Subcontractor shall be responsible for installation and maintenance of all erosion and turbidity controls and the quality and quantity of off-site and runoff discharges. Prior to construction, the Site Subcontractor is responsible for having his dewatering plan and turbidity control plan approved by the project engineer and applicable regulatory agencies. The dewatering and turbidity control plans for agencies requiring such review and approval. Questions concerning applicable techniques should be addressed to those agencies and/or discussed with the project engineer and consultant as needed with the project engineer and appropriate agencies. The Site Subcontractor will be responsible for obtaining any and all necessary permits for such activity, several factors to consider are listed below: City control in excavated materials and/or permeability rates. Depth of cut in ponds, trenches, or utility lines. Ambient ground water levels. Actual rainfall amounts and time of year relative to normal rainy season. Proximity to wetlands, water bodies or offsite properties. 'Class' designation of receiving water bodies (i.e., Outstanding Florida Waters, shellfish harvesting areas, etc.). Density, type, and proximity of upland vegetation to be retained during construction (for use as possible filtration areas). Actual rainfall amounts and time of year relative to normal rainy season. H. Fill height relative to natural grade and length and steepness of the proposed slopes. I. Existing topography and directions of surface flow. J. Type of equipment used. K. Project type. L. Duration of construction activities. M. Separation distance of erosion ponds. N. Ambient quality of surface and groundwater. O. Temporary stockpile locations and heights. <p>At the onset of construction, the Subcontractor, as the party responsible for implementation of the erosion and sediment control plan, shall assess the above described conditions and factors with respect to relative cost effectiveness and select the appropriate methods of protection. A fairly extensive list of techniques are presented below for all of the above conditions. Where necessary, the contractor shall maintain water quality and quantity standards. The construction sequencing should be thought out in advance of initiation to provide adequate protection of water quality.</p> <ol style="list-style-type: none"> Discharges which exceed 29 N.T.U.'s over the background levels are in violation of state water quality standards. Discharges of water quantities which affect offsite properties or may damage wetlands are also prohibited by regulating agencies. The erosion and turbidity control measures shown hereon are the minimum required for agency approval. Additional control and measures may be required due to the Site Subcontractor's construction sequence & unseasonable weather conditions. Any additional measures deemed necessary by the Site Subcontractor shall be included in the lump sum bid with no extras for materials and labor allowed. Hay bales or silt screens shall be installed prior to land clearing to protect water quality and to identify areas of erosion to be protected from clearing activities and maintained for the duration of the project until all soil is stabilized. Floating turbidity barriers shall be in place in flowing streams or in open water lake edges prior to initiation of earthwork and maintained for the duration of the project until all soil is stabilized. No clay material shall be left exposed in any stormwater storage facility. If clay or sandy-clays are encountered, the site sub-contractor shall notify the Engineer immediately. The Engineer shall be notified immediately before proceeding with further excavation. If the Engineer of Record has determined that such soils are non-confining and may be required to meet permit and design conditions, excavation may proceed as written with the approval of the governing agency. If said soils are left exposed at the permitted and designed depth, the Site Subcontractor shall over-excavate the pond's bottom and side slopes by a minimum of twelve (12) inches and backfill with clean sands to help prevent suspension of fine particles in the water column. The installation of temporary erosion control barriers shall be coordinated with the construction of the permanent erosion control features to the extent necessary to assure effective and continuous control of erosion and water pollution throughout the life of the construction phase. The type of erosion control barriers used shall be governed by the nature of the construction operation and soil type that will be exposed. Silt and clayey materials may require solid sediment barriers to prevent water discharge, while sandy materials may need only silt screens or hay bales to prevent erosion. Floating turbidity curtains should generally be used in open water situations. Diversions ditches or swales may be required to prevent turbid stormwater runoff from being discharged to wetlands or other nearby bodies. It may be necessary to employ a combination of barriers, ditches, and other erosion/turbidity control measures if conditions warrant. When the area to be used to remove turbid waters from construction areas, the water shall be treated prior to discharge to the wetlands. Treatment methods include, for example, turbid water being pumped into grassed swales or appropriate upland vegetated areas (other than upland preservation areas and wetlands), sedimentation basins, or confined by an appropriate enclosure such as turbidity barriers or low berms, and kept confined until turbidity levels meet State Water Quality Standards. The permittee shall schedule his operations such that the area of unprotected erodible earth exposed at any time is not larger than the minimum area necessary for efficient construction operation, and the duration of exposed, unprotected construction to the elements shall be as short as practicable. Clearing and grubbing shall be so scheduled and performed such that grading operations can follow immediately thereafter. Grading operations shall be so scheduled and performed that permanent erosion control features can follow immediately thereafter if conditions on the project permit. Water derived from various dewatering methods should be passed through sufficiently wide areas of existing upland vegetation to filter out excess turbidity. If this is not sufficient, the water shall be retained in previously constructed permanent stormwater ponds or else retained in temporary sedimentation basins until the clarity is suitable to allow for its discharge. Plugging the outfalls from completed stormwater ponds may be required to avoid discharge. However, such situations should be monitored closely to preclude berm failure if water levels rise too high. Waste transport systems around the site by the use of internal swales or by pumps and pipes. Sheet flow of newly filled or scraped areas may be controlled or contained by the use of brush barriers, diversion swales, interceptor ditches or low berms. Flow should be directed toward areas where sediment can sufficiently settle out. Exposed soils shall be stabilized as soon as possible, especially slopes leading to wetlands. Stabilization methods include solid soil, seeding and mulching or hydro-mulching to provide a temporary or permanent grass cover much blankets, filter fabrics, etc., can be employed to provide vegetative cover. Energy dissipaters (such as rip rap, a gravel bed, hay bales, etc.) shall be installed at the discharge point of pipes or swales if scouring is observed. Attempt to install roadway curb and gutters as soon as possible to reduce the surface area for erosion to occur. Implement storm drain inlet protection (hay bales or gravel) to limit sedimentation within the stormwater system. Perform inspections and periodic cleaning of sediments which wash out into the streets until all soil is stabilized. Water discharge vehicles from impounded areas and temporary sedimentation basins shall be restricted to avoid scouring in receiving areas. If water clarity does not reduce to state standards rapidly enough in holding ponds, it may be possible to use chemical agents such as alum to flocculate or coagulate the sediment particles. Hay bales, silt screens, or gravel beds can be added around the pipe or swale discharge points to help clarify discharges. Spreader swales may help dissipate cloudy water prior to contact with wetlands. All fuel storage areas or other hazardous storage areas shall conform to accepted state or federal criteria for such containment areas. Vehicle or equipment washdown areas will be sufficiently removed from wetlands or offsite areas. Fugitive dust control (primarily by using water spray trucks) shall be employed as needed to control windborn emissions. If the above controls remain ineffective in precluding release of turbid water, especially during pond or utility line dewatering, then the contractor may be compelled to use a vertical dewatering system such as well points or sock drains to withdraw groundwater which may already be clear enough to allow for direct discharge to wetlands. Ongoing inspections and periodic maintenance by the Site Subcontractor shall occur throughout construction as necessary to insure the above methods are working suitably. This may be needed daily, if conditions so warrant. Site Subcontractors are encouraged to obtain and thoroughly review The Florida Development Manual: A Guide to Sound Land and Water Management, which was developed by the State of Florida Department of Environmental Protection in 1988. This provides fair in-depth discussions of recommended techniques and also provides specific design and technical standards. A copy of this document is available for review at Heidt Design, LLC. The contractor will perform daily inspections of all on-site wetlands within the construction area to ensure that water levels within those wetlands are not excessively impounded prior to the time when the permitted control structure or outlet is built. Water levels significantly above normal should be corrected at a frequency that prevents a change in the vegetative character or health of any wetlands. Prior to commencement of clearing & grubbing or any soil disturbance, contractor shall coordinate with Heidt Design to schedule a pre-construction soil erosion and sediment control inspection with the Pasco County Stormwater Management Division. <p>POND/LAKE EXCAVATION NOTE:</p> <p>No excavation shall extend below the permitted design depths/elevations shown on the drawings, unless additional testing supports otherwise and no lower semi-confining unit clayey soil material and/or no limestone materials shall be excavated, regardless if these materials are encountered within the permitted excavation depths/elevations. If any lower semi-confining unit clayey soil materials or limestone materials are encountered above the permitted depths/elevations, then excavation operations shall cease in the general area and the Engineer of Record shall be notified immediately.</p> <p>WETLANDS NOTE:</p> <p>There are no wetland impacts proposed and therefore, no mitigation required.</p> <p>"Conservation Area" designation is given to all protected wetlands per Pasco County requirements. They are not designated as "Conservation Easements" for SWFWMD compliance.</p> <p>Wetland lines permitted under ERP No. 26980.002</p> <p>IMPORTED FILL MATERIAL:</p> <p>No material shall be hauled from the site.</p> <p>ON-SITE MATERIAL:</p> <p>CUT VOLUME = 624,120 CU YDS FILL VOLUME = 623,426 CU YDS</p>				
C		<p>SOIL REUSE REQUIREMENTS</p> <p>At least the following six (6) types of materials are present on-site that require proper handling/treatment by the Contractor, during the course of site development/construction activities, in accordance with the noted reuse requirements for each type. Although some soil material quality control testing will be randomly and periodically performed by the project Geotechnical Consultant, as required, working for the Owner, it is the Contractor's sole responsibility to reuse onsite soil materials as described and specified below. All discovered or future filling or material reuse work onsite not in accordance or compliance with these notes, or any future adverse impacts or consequences resulting from the Contractor's failure to properly reuse soil materials onsite as specifically described below, will be the Contractor's sole responsibility for remedy and repair at his cost. If the Contractor has any questions regarding any of the soil materials onsite, the project Geotechnical reports (which he needs to obtain from the Owner's Geotechnical Consultant Engineer), or any questions associated with the notes below, it is presumed that the Contractor will satisfactorily resolve such questions/concerns prior to site demolition, clearing, grubbing, stripping and excavation operations begin.</p> <p>Please note, local, state and federal rules, laws, and regulations prohibiting soil reuse as described below shall take precedence and shall be followed to the fullest extent:</p> <ol style="list-style-type: none"> Site Demolition Debris (Site demolition debris, not generally considered an environmental/contamination hazard, includes such items as wood pieces, concrete pieces, plastic pipe pieces, certain metal/steel pieces, or similar. If any such debris or other demolition debris is considered an environmental/contamination hazard, or if burial onsite of such materials is prohibited by the governing environmental agency, then all such materials shall be hauled off site by the Contractor for proper disposal, in accordance with all applicable governing environmental agency requirements. In no case, shall any such debris materials remain, or be placed by the Contractor, beneath any type of structure, pavement, roadway, house, building, pipeline, slab, etc.) All Site Demolition Debris shall be removed from the site development and disposed of properly in accordance with all applicable governing environmental agency requirements. Clearing and Grubbing Debris (Site clearing and grubbing debris includes all larger organic materials, such as trees, stumps, limbs, brush, vegetation, or similar, all such materials must be either "burned" or "mulched" by the Contractor prior to reuse or disposal onsite.) <p>If acceptable to the governing environmental agency, then all such "burned" or "mulched" site clearing/grubbing debris, if approved in writing first by the Owner/Geotechnical Consultant/Engineer, could be:</p> <ol style="list-style-type: none"> placed as "muck" material surface dressing in future landscape areas, stockpiling of such materials (amounts/locations), if acceptable, will be directed by the Owner/Landscape Consultant; placed in temporarily excavated littoral shelf areas in selected stormwater ponds, or in temporarily excavated selected wetland mitigation ponds, in either case not in side banks and not below the permitted design depth of the pond, or such debris could be buried in temporarily excavated passive recreation/park areas (at least 30 feet from any structure) at approved depths/elevations, but all these disposal areas will require adequate soil mixing (mix soil with the organic materials) and then refilling (with compaction) to required design grades; placed along the bottom of selected floodplain mitigation ponds (not in side banks), not below the permitted excavation depth of the pond, but will require adequate soil cover; placed along the bottom of selected deeper stormwater ponds (not in side banks), not below the permitted design depth of the pond, but will require adequate soil cover. <p>All organic debris burial areas in stormwater pond areas and floodplain mitigation pond areas will require adequate soil cover (with compaction) by the Contractor, meaning at least an adequate weight/thickness of soil material overtop the buried organic debris, such that there will be no future floating up of debris; and for all organic debris burial areas in littoral shelf areas, wetland mitigation pond areas, and passive recreation/park areas, adequate soil/organics mixing (with compaction) will be necessary by the Contractor, such that no significant future unacceptable settlement of a littoral shelf area, created wetland area, or park/grassed area will occur.</p> <p>If any of these procedures are contemplated by the Contractor, then the Contractor shall notify the Owner/Geotechnical Consultant/Engineer in writing, at the start of construction, with some specific information, including the estimated quantity and types of materials, to which stormwater ponds, floodplain mitigation ponds, wetland mitigation ponds, or passive recreation/park/landscape berm areas they propose to use for this type of organic material disposal, and what approximate elevations will be the top and bottom of the organic material.</p> <ol style="list-style-type: none"> Topsoil/Soil Strippings (Typically generated from upland areas, after demolition/clearing/grubbing operations, stripping of surficial organics/topsoils being a requirement over at least all structure, building, concrete slab and pavement areas prior to filling to accommodate settlement, includes topsoils and organic laden sands; those topsoil/organic laden sand materials being suitable or acceptable for reuse by the Contractor as building pad fill, structural fill, roadway embankment fill, and pipeline or manhole excavation backfill.) <p>If acceptable to the governing environmental agency, all such topsoil/organic laden sand materials, if approved in writing first by the Owner/Geotechnical Consultant/Engineer, could be:</p> <ol style="list-style-type: none"> placed as fill in new (larger) landscape/grass common areas or landscape berm areas (with compaction), stockpiling of such "topsoil/organic laden sand materials" (amounts/locations), if acceptable, will be directed by the Owner/Landscape Consultant; placed in temporarily excavated littoral shelf areas in selected stormwater ponds, or in temporarily excavated selected wetland mitigation ponds, in either case not in side banks and not below the permitted design depth of the pond, or such topsoil/organic laden sand materials could be buried in temporarily excavated passive recreation/park areas (at least 30 feet from any structure) at approved depths/elevations, but all these disposal areas will require refilling (with compaction) to required design grades; placed along the bottom of selected floodplain mitigation ponds (not in side banks), not below the permitted excavation depth of the pond, but will require adequate soil cover; placed along the bottom of selected deeper stormwater ponds (not in side banks), not below the permitted design depth of the pond, but will require adequate soil cover. <p>In all instances, the minimum pond depth (including floodplain and wetland mitigation areas) shall be no less than required by the Engineer.</p> <p>All organic debris burial areas in stormwater pond areas and floodplain mitigation pond areas will require adequate soil cover (with compaction) by the Contractor, meaning at least an adequate weight/thickness of soil material overtop the buried organic debris, such that there will be no future floating up of debris; and for all organic debris burial areas in littoral shelf areas, wetland mitigation pond areas, and passive recreation/park areas, adequate soil/muck mixing (with compaction) will be necessary by the Contractor, such that no significant future unacceptable settlement of a littoral shelf area, created wetland area, or park/grassed area will occur.</p> <p>If any of these procedures are contemplated by the Contractor, then the Contractor shall notify the Owner/Geotechnical Consultant/Engineer in writing, at the start of construction, with some specific information, including the estimated quantity and types of materials, to which stormwater ponds, floodplain mitigation ponds, wetland mitigation ponds, or passive recreation/park areas they propose to use for this type of organic debris disposal, and what approximate elevations will be the top and bottom of the organic debris.</p> <ol style="list-style-type: none"> Muck/Peat Organic Materials (Typically generated from wetland or lowland areas, or similar areas, permitted for impact or displacement, including excavation of unsuitable organic materials and refilling with suitable sandy soils to accommodate development; includes significant organic peat materials, organic sandy muck materials, and mucky or organic sand materials, designated either Pt or A-3, per the Unified and AASHTO Soil Classification Systems, respectively; those organic materials whose presence, or placement by the Contractor, is unacceptable beneath any type of structure, pavement, roadway, house, building, pipeline, slab, etc.) <p>If any of these procedures are contemplated by the Contractor, then the Contractor shall notify the Owner/Geotechnical Consultant/Engineer in writing, at the start of construction, with some specific information, including the estimated quantity and types of materials, to which stormwater ponds, floodplain mitigation ponds, wetland mitigation ponds, passive recreation/park areas, or landscape berm areas they propose to use for this type of organic debris disposal, and what approximate elevations will be the top and bottom of the organic debris.</p> <ol style="list-style-type: none"> Non-Structural Clayey Sand/Clay Materials (Typically generated from pond/lake excavations or from utility pipeline/manhole excavations; such clayey sand/clay materials, with typically 40% fines or more passing the No. 200 sieve, designated either SC, CL, CH or A-4 to A-7, per the Unified and AASHTO Soil Classification Systems, respectively; such clayey sand/clay materials being unsuitable or acceptable for reuse by the Contractor as building pad fill, structural fill, roadway embankment fill, and pipeline or manhole excavation backfill.) 				
	B	<p>GENERAL SITE NOTES</p> <ol style="list-style-type: none"> Erosion control devices specified herein shall be installed prior to site construction and shall be maintained throughout construction until site is permanently stabilized. If during construction activities any evidence of historic resources, including but not limited to aboriginal or historic pottery, prehistoric stone tools, bone or shell tools, historic trash pits, or historic building foundations, are discovered work shall come to an immediate stop and the Florida Department of historic resources (state historic preservation officer) and Pasco county shall be notified within two working days of the resources found on site. Any off site disturbance shall be restored to the pre-construction condition or better. As applicable, the owner/developer shall provide copies of the required permits from the respective governing agencies, prior to issuance of the site development permit (SDP). If during the construction activities any evidence of the presence of state and federally protected plant and/or animal species are discovered, work shall come to an immediate stop and Pasco county shall be notified within two working days of the plant and/or animal species found on site. These plans were prepared with the benefit of and in conformance to the geotechnical recommendations contained in the reports by Faulkner Engineering Services, Inc. entitled as follows: Report of Limited Geotechnical Exploration (Dated September, 2005). This project lies within flood zones A, AE, & X, according to flood insurance rate maps for Pasco County, FL, Federal Emergency Management Agency (FEMA) - Flood Insurance Rate Map (FIRM) community panel No. 12101C 0258F, 12101C 0259F, 12101C 0269F, & 12101C 0267F, Dated August 28, 2008 and issued by the federal emergency management agency. 				
A		<p>STORM WATER POLLUTION PREVENTION PLAN</p> <p>Contained on these plans and within the following notes is a storm water pollution prevention plan (swppp) which has been developed by Heidt Design, LLC in accordance with the Florida Department of Environmental Protection's (FDEP) "National Pollutant Discharge Elimination System" (NPDES) generic permit for stormwater discharge from large and small construction activities.</p> <p>The following entities are identified as team members of "SWPPP": Heidt Design, LLC, the developer as identified in the title box of these plans, and the site contractor and his sub-contractors. Each team member has specific responsibilities and obligations. In general, all team members, with regard to their involvement and responsibilities on the project, are to implement all necessary storm water management controls to assure compliance with the NPDES generic permit for storm water discharges from construction activities, the Southwest Florida Water Management District Permit, the applicable local governing agency (i.e. Pasco County) and the guidelines listed in the SWPPP. The duties and responsibilities of the team members as they pertain to the SWPPP are as follows:</p> <p>HEIDT DESIGN, LLC:</p> <p>A. Develop SWPPP including, but not limited to, retention/detention ponds, control structures, erosion control methods and locations and stabilization criteria. This design is included within these construction plans and the following notes and instructions.</p> <p>B. Submit and obtain the necessary design related storm water permits from the Florida Department of Environmental Protection, the Southwest Florida Water Management District and other applicable governmental bodies.</p> <p>C. Upon notification by the developer of his intent to commence construction, submit a copy of intent to the FDEP on behalf of the developer and copy the contractor including SWPPP certification and notice of the permit.</p> <p>D. Submit to SWFWMD and the operator of the municipal separate storm water system, if applicable, a letter of construction commencement.</p> <p>E. Complete and submit a notice of termination and certification for developer. The NOT's shall be submitted no more than 30 days after:</p> <p>(a) Completion of the project and final stabilization of the site or</p> <p>(b) When responsibility for the site has ended. Final stabilization as defined by EPA is when all soil disturbing activities at the site have been completed and a uniform (e.g. evenly distributed, without large bare areas) perennial vegetative cover with a density of 70% of the native background vegetative cover for the area has been established on all upland areas and areas not covered by permanent structures. As an alternative, equivalent permanent stabilization measures (such as straw, gabions, or geotextiles) may be employed. The client shall notify Heidt Design, LLC when one of these criteria has been met.</p> <p>CONTRACTOR:</p> <p>A. Sign and return to Heidt a contractor certification form certifying your understanding of and willingness to comply with the Storm Water Pollution Prevention Plan no later than 48 hours prior to commencement of construction. The site sub-contractor shall certify to Heidt Design, LLC that the contractor that they understand and shall comply with the NPDES Permit and SWPPP. A record of these certifications shall be maintained by the contractor on site.</p> <p>B. During construction, assure compliance with the designed Storm Water Pollution Prevention plans prepared by Heidt Design, LLC and the NPDES Generic Permit for storm water discharges from large and small construction activities.</p> <p>C. Maintain a copy of the construction plans, which include the Storm Water Pollution Prevention Plan, the NOI, and all inspection reports and certifications on site.</p> <p>D. Undertake all reasonable Best Management Practices (BMP's) to assure that silted or otherwise polluted storm water is not allowed to discharge from the site during all phases of construction. Stabilization BMP's that may be used include:</p> <p>Temporary or permanent seeding, mulching, geotextiles, sodding, vegetative buffer strips, protection of trees and preservation of mature vegetation. Structural erosion and sediment control BMP's that may be used include: straw bale dikes, silt fences, earth dikes, brush barriers, drainage swales, check dams, subsurface drain, pipe slope drain, level spreaders, storm drain inlet protection, outlet protection, sediment traps, and temporary sediment basins. Detention ponds may also be used as temporary sediment basins. Additional BMP's that may need to be implemented include: providing protected storage areas for chemicals, paints, solvents, fertilizers, and other potentially toxic materials. Providing waste receptacles at convenient locations and providing regular collection of wastes, including building material wastes. Minimizing off-site tracking of sediments. Making adequate preparations, including training and equipment to contain spills of oil and hazardous materials. Complying with applicable state or local waste disposal, sanitary sewer or septic system regulations and the use of appropriate pollution prevention measures for allowable non-storm water components of discharge.</p> <p>E. Notify Heidt Design, LLC and the developer in writing of any non-storm water pollution sources which are being stored, or otherwise used during the construction of the project, i.e., fertilizers, fuels, pesticides, other chemicals. This notification should be accompanied with the contractor's design and methods to prevent pollution run-off from these sources.</p> <p>F. Develop a maintenance and inspection plan which includes, but is not limited to the following:</p> <p>(a) The specific areas to be inspected and maintained that includes all the disturbed areas and material storage areas of the site.</p> <p>(b) The erosion and sediment controls identified in the swppp to be maintained and inspected and those additional controls that the contractor deems necessary.</p> <p>(c) Maintenance procedures.</p> <p>(d) The procedure to follow if additional work is required or whom to call.</p> <p>(e) Inspections and maintenance tasks.</p> <p>(f) The personnel assigned to each task.</p> <p>The following shall be inspected a minimum of once a week or within 24 hours after 0.50 inches of rainfall:</p> <p>Stabilization measures (once a month if fully stabilized).</p> <p>Structural controls.</p> <p>Discharge points.</p> <p>Construction entrances and exits.</p> <p>Areas used for storage of exposed materials.</p> <p>An inspection form shall be completed for each inspection. Any permit violations should be noted and corrective measures shall be taken no later than 7 days after the inspection occurred. If revisions to the SWPPP are needed, a report form for changes in the SWPPP shall be completed and a copy sent to Heidt Design, LLC the original shall be kept on-site as documentation of the change. If the inspection passes, a certification that the facility is in compliance with the SWPPP and the NPDES Permit must be signed by a duly authorized representative of the principal executive officer of the operator of the SWPPP with one of the following qualifications:</p> <ol style="list-style-type: none"> Has successfully completed the Florida Stormwater, Erosion and Sediment Control Inspector Training Program. Successfully completed a similar training program. Has enough practical on the job training to be qualified to perform the inspections. Retain inspection reports and certifications for at least three years. <p>G. Site stabilization measures shall be initiated as soon as practical but in no case more than 7 days, in portions of the site where construction activities have temporarily or permanently ceased.</p> <p>H. Releases in excess of reportable quantities.</p> <ol style="list-style-type: none"> The discharge of hazardous substances (as in the stormwater discharge) from a facility or activity shall be prevented or minimized in accordance with the applicable Stormwater Pollution Prevention Plan for the facility or activity. This permit does not relieve the operator of the reporting requirements of 40 cfr part 117 and 40 cfr part 302. Where a release containing a hazardous substance in an amount equal to or in excess of a reporting quantity established under either 40 cfr 117 or 40 cfr 302, occurs during a 24-hour period: The operator is required to notify the State Warning Point (800-210-0519 or 850-413-9911) as soon as she or she has knowledge of the discharge; The operator shall submit within 14 calendar days of knowledge of the release a written description of the release (including the type and estimate of the amount of material released), the date that such release occurred, the circumstances leading to the release, and remedial steps to be taken, to the Florida Department of Environmental Protection, NPDES Stormwater Section, Mail Station 2500, 2600 Blair Stone Road, Tallahassee, Florida 32309-2400; and The Stormwater Pollution Prevention Plan required under part V of this permit must be modified within 14 calendar days of knowledge of the release to provide a description of the release, the circumstances leading to the release, and the date of the release. In addition, the plan must be reviewed to identify measures to prevent the recurrence of such releases and to respond to such releases, and the plan must be modified where appropriate. <p>2. This permit does not authorize the discharge of hazardous substances or oil resulting from an on-site spill.</p>				



HEIDT DESIGN
Civil Engineering • Planning & GIS
Transportation Engineering
Ecological Services • Landscape Architecture

8506-B Breckenridge Pkwy.
Tampa, Florida 33610
Office: 813-253-7521
Fax: 813-464-7239

www.HeidtDesign.com

MIRADA PHASE 1 MASS GRADING PLAN

GENERAL NOTES

PREPARED FOR: METRO DEVELOPMENT GROUP, LLC

NO.	REVISION SUBMITTAL	DATE	DESCRIPTION
1	REVIEW SUBMITTAL	12/16/2015	1024
2	DESIGN		
3			
4			
5			
6			

PROJECT NO.: CRP CR 1024

FILE: GN0TES

DESIGN BY: RUSSUSS

DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER


EDWIN J. ROGERS

DATE: _____

REGISTRATION NO. 50082

C-101

CONTRACTOR: HEIDT DESIGN, LLC. ALL RIGHTS RESERVED. NO INFORMATION OR CONSTRUCTION INFORMATION IS TO BE RELEASED FROM HEIDT DESIGN, LLC IN ANY MANNER. OWNER IS HEREBY WARRANTED SPECIFICALLY TO GOVERNMENT AGENCIES: THIS DOCUMENT IS THE EXCLUSIVE PROPERTY OF HEIDT DESIGN, LLC. ANY REUSE OF THIS DOCUMENT IS PROHIBITED.



NOTE:
 DEVELOPMENT PATTERN (FUTURE STREETS AND LOTS) AS SHOWN WITHIN THE MASS GRADING LIMITS IS CONCEPTUAL AND SHOWN FOR CONTEXT.

MASS-GRADE AREA
 FUTURE LAND USE: RES-3 & RES-6

MASS-GRADE AREA
 ZONING DISTRICT: MPUD

ELEVATIONS BASED ON:
 NORTH AMERICAN VERTICAL DATUM
 CONVERSION:
 NAVD 88 TO NGVD 29 = +0.85

HEIDT DESIGN
 Civil Engineering • Planning & GIS
 Transportation Engineering
 Ecological Services • Landscape Architecture

5806-B Breckenridge Pkwy.
 Tampa, Florida 33610
 Office: 813-253-5311
 Fax: 813-464-7629
 www.HeidtDesign.com

Engineering Certificate of Authorization No. 28792
 Landscape Architecture Certificate of Authorization No. LC16000405

MIRADA
 PHASE 1 MASS GRADING PLAN
 AERIAL SITE PLAN

PREPARED FOR:
 METRO DEVELOPMENT GROUP, LLC

NO.	DATE	REVISION	DESCRIPTION


NO.	DATE	REVISION	DESCRIPTION
1	12/15/2015	REVIEW SUBMITTAL	

PROJECT NO: CRP CR 1024
 FILE: ASP
 DESIGN BY: RUSSUM
 DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER
 EDWIN J. ROGERS
 DATE: _____
 REGISTRATION NO. 50082

C-102

R:\MIRADA\PHASE 1 MASS GRADING\ENGINEERING\DWG - C-102 20141215 13 2:48 PM ERIC FRANCIS



GRAPHIC SCALE: 1" = 300'
LEGEND

- EXISTING WETLAND BOUNDARY
- - - 25' WETLAND SETBACK
- PROPERTY BOUNDARY LIMITS
- MASS GRADING PROJECT LIMITS
- PROPOSED POND LIMITS
- ▨ 100YR FLOOD PLAIN LIMITS ZONE A AND AE
ALL OTHER AREAS ARE ZONE X
- □ □ □ □ SILT FENCE (DISTURBANCE LIMITS)
- DISTURBED AREA
- PARCEL LIMITS

*EXISTING CURLEY ROAD (C.R. 577) IS AN EXISTING 2-LANE PUBLIC ROADWAY WITH 24 FEET OF PAVEMENT ARRANGED IN A RURAL CROSS SECTION WITHIN 66 FEET OF RIGHT-OF-WAY; FUTURE CURLEY ROAD IS A 6-LANE URBAN ARTERIAL PUBLIC ROADWAY WITHIN 166 FEET RIGHT-OF-WAY.

NOTE: NO CONSTRUCTION ACTIVITY SHALL TAKE PLACE WITHIN 50 FEET OF WELL LOCATIONS SHOWN ON THESE PLANS UNTIL THE WELL HAS BEEN PROPERLY ABANDONED IN ACCORDANCE WITH SOUTHWEST FLORIDA WATER MANAGEMENT DISTRICT REGULATIONS BY A CERTIFIED WELL CONTRACTOR

ELEVATIONS BASED ON:
NORTH AMERICAN VERTICAL DATUM
CONVERSION:
NAVD 88 TO NGVD 29 = +0.85

HEIDT DESIGN
Civil Engineering • Planning & GIS
Transportation Engineering
Ecological Services • Landscape Architecture
Engineering Business Certificate of Authorization No. 28792
Landscape Architecture Certificate of Authorization No. LC20000405

5806-B Breckenridge Pkwy.
Tampa, Florida 33610
Office: 813-253-5311
Fax: 813-464-7629
www.HeidtDesign.com

MIRADA
PHASE I MASS GRADING PLAN
OVERALL MASS GRADING PLAN

PREPARED FOR: METRO DEVELOPMENT GROUP, LLC



NO.	DATE	DESCRIPTION
1	12/15/2015	REVIEW SUBMITTAL

PROJECT NO: CRP CR 1024
FILE: MP
DESIGN BY: RUSSUM
DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER
EDWIN J. ROGERS
DATE: _____
REGISTRATION NO. 50082

C-200

R:\MIRADAPHASE I\MASS GRADING\ENGINEERING\DWG - C-200 OVERALL MASS GRADING PLAN 2014/12/13 2:48 PM ERIC FRANCIS




ELEVATIONS BASED ON:
NORTH AMERICAN VERTICAL DATUM
CONVERSION:
NAVD 88 TO NGVD 29 = +0.85

DRAINAGE LEGEND

EXISTING	PROPOSED	DESCRIPTION
x	●	SPOT ELEVATION
-15-	—	CONTOUR
→	→	DIRECTION OF SURFACE FLOW
□□□□□□	□□□□□□	STAKED EROSION CONTROL REPRESENTS THE SWFWMD PROJECT LIMITS AND THE LIMITS OF CLEARING AND FILLING
---	---	WETLAND LINE
---	---	25' WETLAND CONS. AREA SETBACK / LANDWARD EXTENT OF UPLAND BUFFER
---	---	100YR FLOOD LINE
○	○	POND BORING
---	---	PHASE 1 FILL LIMITS
---	---	MASS GRADING FLOW LINE
---	---	MASS GRADING RIDGE

EXISTING TOPOGRAPHIC SURVEY PROVIDED BY D.C. JOHNSON & ASSOCIATES, DATED 12/12/2014.

THIS PROJECT LIES IN FLOOD ZONES A, AE, & X ACCORDING TO FLOOD INSURANCE RATE MAPS FOR PASCO COUNTY, FLORIDA, FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) - FLOOD INSURANCE RATE MAP (FIRM) COMMUNITY PANEL NOS. 12101C 0258F, 12101C 0259F, 12101C 0266F, & 12101C 0267F, DATED AUGUST 28, 2008 AND ISSUED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY.



HEIDT DESIGN
Civil Engineering • Planning & GIS
Transportation Engineering
Ecological Services • Landscape Architecture
Engineering Business Certificate of Authorization No. 28782
Landscape Architecture Certificate of Authorization No. LC26000405

5806-B Breckenridge Pkwy.
Tampa, Florida 33610
Office: 813-253-5311
Fax: 813-464-7629
www.HeidtDesign.com



MIRADA
PHASE 1 MASS GRADING PLAN
MASS GRADING PLAN
PREPARED FOR: METRO DEVELOPMENT GROUP, LLC

NO.	DATE	DESCRIPTION
1	12/15/2015	REVIEW SUBMITTAL

PROJECT NO: CRP CR 1024
FILE: BASE-PHASE 1
DESIGN BY: RUSSUM
DRAWN BY: FRANCIS
FLORIDA PROFESSIONAL ENGINEER
EDWIN J. ROGERS
DATE: _____
REGISTRATION NO. 50082
C-202

R:\MIRADA\PHASE 1 MASS GRADING\ENGINEERING\BASE-PHASE 1.DWG C-202 MASS GRADING PLAN 2014/12/13 2:50 PM ERIC FRANCIS

COPYRIGHT © HEIDT DESIGN, LLC. ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT OR ANY INFORMATION CONTAINED HEREIN MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT PERMISSION IN WRITING FROM HEIDT DESIGN, LLC. IN ADVANCE. CONSENT IS HEREBY GRANTED SPECIFICALLY TO GOVERNMENT AGENCIES TO REPRODUCE THIS DOCUMENTATION IN CONNECTION WITH THE DISHWAIT.




DRAINAGE LEGEND

EXISTING	PROPOSED	DESCRIPTION
x	●	SPOT ELEVATION
-15-	—15—	CONTOUR
→	→	DIRECTION OF SURFACE FLOW
□□□□□□	□□□□□□	STAKED EROSION CONTROL REPRESENTS THE SWF/MD PROJECT LIMITS AND THE LIMITS OF CLEARING AND FILLING
---	---	WETLAND LINE
---	---	25' WETLAND CONS. AREA SETBACK / LANDWARD EXTENT OF UPLAND BUFFER
---	---	100YR FLOOD LINE
○	○	POND BORING
---	---	PHASE 1 FILL LIMITS
---	---	MASS GRADING FLOW LINE
---	---	MASS GRADING RIDGE

EXISTING TOPOGRAPHIC SURVEY PROVIDED BY D.C. JOHNSON & ASSOCIATES, DATED 12/1/2014.

THIS PROJECT LIES IN FLOOD ZONES A, AE, & X ACCORDING TO FLOOD INSURANCE RATE MAPS FOR PASCO COUNTY, FLORIDA, FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) - FLOOD INSURANCE RATE MAP (FIRM) COMMUNITY PANEL NOS. 12101C 0258F, 12101C 0259F, 12101C 0266F, & 12101C 0267F, DATED AUGUST 28, 2008 AND ISSUED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY.

KEY MAP



HEIDT DESIGN
 Civil Engineering • Planning & GIS
 Transportation Engineering
 Ecological Services • Landscape Architecture
 Engineering Business Certificate of Authorization No. 28792
 Landscape Architecture Certificate of Authorization No. LC26000405

5806-B Breckenridge Pkwy
 Tampa, Florida 33610
 Office: 813-253-5311
 Fax: 813-464-7629
 www.HeidtDesign.com

MIRADA
PHASE 1 MASS GRADING PLAN
 MASS GRADING PLAN
 PREPARED FOR: METRO DEVELOPMENT GROUP, LLC


NO.	DATE	DESCRIPTION
1	12/15/2015	REVIEW SUBMITTAL

PROJECT NO: CRP CR 1024
 FILE: BASE-PHASE 1
 DESIGN BY: RUSSUM
 DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER
EDWIN J. ROGERS
 DATE: _____
 REGISTRATION NO. 50082

C-203

R:\MIRADA\PHASE 1 MASS GRADING\ENGINEERING\PHASE 1.DWG - C-203 MASS GRADING PLAN 2014/12/13 13:25:11 PM ERIC FRANCIS



ELEVATIONS BASED ON:
NORTH AMERICAN VERTICAL DATUM
CONVERSION:
NAVD 88 TO NGVD 29 = +0.85



0 100 200
GRAPHIC SCALE: 1" = 100'

DRAINAGE LEGEND

EXISTING	PROPOSED	
x	● 105.0	SPOT ELEVATION
-15-	— 15 —	CONTOUR
→	→	DIRECTION OF SURFACE FLOW
□□□□□□	□□□□□□	STAKED EROSION CONTROL REPRESENTS THE SWIFMD PROJECT LIMITS AND THE LIMITS OF CLEARING AND FILLING
---	---	WETLAND LINE
---	---	25' WETLAND CONS. AREA SETBACK / LANDWARD EXTENT OF UPLAND BUFFER
---	---	100YR FLOOD LINE
○ PB-#	○ PB-#	POND BORING
■	■	PHASE 1 FILL LIMITS
---	---	MASS GRADING FLOW LINE
---	---	MASS GRADING RIDGE

EXISTING TOPOGRAPHIC SURVEY PROVIDED BY D.C. JOHNSON & ASSOCIATES, DATED 12/1/2014.

THIS PROJECT LIES IN FLOOD ZONES A, AE, & X ACCORDING TO FLOOD INSURANCE RATE MAPS FOR PASCO COUNTY, FLORIDA, FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) - FLOOD INSURANCE RATE MAP (FIRM) COMMUNITY PANEL NOS. 12101C 0258F, 12101C 0259F, 12101C 0266F, & 12101C 0267F, DATED AUGUST 28, 2008 AND ISSUED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY.



HEIDT DESIGN
Civil Engineering • Planning & GIS
Transportation Engineering
Ecological Services • Landscape Architecture
Engineering Business Certificate of Authorization No. LC26000405
Landscape Architecture Certificate of Authorization No. LC26000405

5806-B Breckenridge Pkwy
Tampa, Florida 33610
Office: 813-253-5311
Fax: 813-464-7629
www.HeidtDesign.com

MIRADA
PHASE 1 MASS GRADING PLAN

MASS GRADING PLAN

PREPARED FOR: METRO DEVELOPMENT GROUP, LLC



DATE	DESCRIPTION
12/15/2015	REVIEW SUBMITTAL

PROJECT NO: CRP CR 1024
FILE: BASE-PHASE_1
DESIGN BY: RUSSUM
DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER
EDWIN J. ROGERS
DATE: _____
REGISTRATION NO. 50082

C-204

© 2015 HEIDT DESIGN, LLC. ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT OR ANY CONTENTS HEREIN MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT PERMISSION IN WRITING FROM HEIDT DESIGN, LLC. IN ADVANCE. CONSENT IS HEREBY GRANTED SPECIFICALLY TO GOVERNMENT AGENCIES TO REPRODUCE THIS DOCUMENTATION FOR OFFICIAL USE ONLY.




DRAINAGE LEGEND

EXISTING	PROPOSED	DESCRIPTION
x	●	SPOT ELEVATION
-15-	—15—	CONTOUR
→	→	DIRECTION OF SURFACE FLOW
□□□□□□	□□□□□□	STAKED EROSION CONTROL REPRESENTS THE SWFWMD PROJECT LIMITS AND THE LIMITS OF CLEARING AND FILLING
---	---	WETLAND LINE
▨	▨	25' WETLAND CONS. AREA SETBACK / LANDWARD EXTENT OF UPLAND BUFFER
---	---	100YR FLOOD LINE
○	○	POND BORING
▭	▭	PHASE 1 FILL LIMITS
---	---	MASS GRADING FLOW LINE
---	---	MASS GRADING RIDGE

EXISTING TOPOGRAPHIC SURVEY PROVIDED BY D.C. JOHNSON & ASSOCIATES, DATED 12/12/2014.

THIS PROJECT LIES IN FLOOD ZONES A, AE, & X ACCORDING TO FLOOD INSURANCE RATE MAPS FOR PASCO COUNTY, FLORIDA, FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) - FLOOD INSURANCE RATE MAP (FIRM) COMMUNITY PANEL NOS. 12101C 0258F, 12101C 0259F, 12101C 0266F, & 12101C 0267F, DATED AUGUST 28, 2008 AND ISSUED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY.



HEIDT DESIGN
 Civil Engineering • Planning & GIS
 Transportation Engineering
 Ecological Services • Landscape Architecture
 Engineering Business Certificate of Authorization No. 28792
 Landscape Architecture Certificate of Authorization No. LC26000405

5806-B Breckenridge Pkwy
 Tampa, Florida 33610
 Office: 813-253-5311
 Fax: 813-464-7629
 www.HeidtDesign.com

MIRADA
 PHASE 1 MASS GRADING PLAN

MASS GRADING PLAN

PREPARED FOR: **METRO DEVELOPMENT GROUP, LLC**



NO.	DATE	DESCRIPTION
1	12/15/2015	REVIEW SUBMITTAL

PROJECT NO: CRP CR 1024
 FILE: BASE-PHASE 1
 DESIGN BY: RUSSUM
 DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER
 EDWIN J. ROGERS
 DATE: _____
 REGISTRATION NO. 50082

C-205

R:\MIRADA\PHASE 1 MASS GRADING\ENGINEERING\PHASE 1 DWG - C-205 MASS GRADING PLAN 2014121513251.PN ERIC FRANCIS
 C:\PROGRAMS\HEIDT DESIGN\PROJECTS\CRP CR 1024\PHASE 1 MASS GRADING\ENGINEERING\PHASE 1 DWG - C-205 MASS GRADING PLAN 2014121513251.PN ERIC FRANCIS
 HAS BEEN PRINTED FROM HEIDT DESIGN, LLC IN ADVANCE. COMMENT IS HEREBY GRANTED SPECIFICALLY TO GOVERNMENT AGENCIES FOR PURPOSES OF THE FLORIDA PUBLIC RECORDS ACT.




DRAINAGE LEGEND


EXISTING	PROPOSED	DESCRIPTION
x	●	SPOT ELEVATION
-15-	-15-	CONTOUR
→	→	DIRECTION OF SURFACE FLOW
□□□□□□	□□□□□□	STAKED EROSION CONTROL REPRESENTS THE SWIFWMD PROJECT LIMITS AND THE LIMITS OF CLEARING AND FILLING
---	---	WETLAND LINE
---	---	25' WETLAND CONS. AREA SETBACK / LANDWARD EXTENT OF UPLAND BUFFER
---	---	100YR FLOOD LINE
○	○	POND BORING
■	■	PHASE 1 FILL LIMITS
---	---	MASS GRADING FLOW LINE
---	---	MASS GRADING RIDGE

EXISTING TOPOGRAPHIC SURVEY PROVIDED BY D.C. JOHNSON & ASSOCIATES, DATED 12/1/2014.

THIS PROJECT LIES IN FLOOD ZONES A, AE, & X ACCORDING TO FLOOD INSURANCE RATE MAPS FOR PASCO COUNTY, FLORIDA, FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) - FLOOD INSURANCE RATE MAP (FIRM) COMMUNITY PANEL NOS. 12101C 0258F, 12101C 0259F, 12101C 0266F, & 12101C 0267F, DATED AUGUST 28, 2008 AND ISSUED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY.



KEY MAP



5806-B Breckenridge Pkwy
Tampa, Florida 33610
Office: 813-253-5311
Fax: 813-464-7629
www.HeidtDesign.com

MIRADA
PHASE 1 MASS GRADING PLAN
MASS GRADING PLAN
PREPARED FOR: METRO DEVELOPMENT GROUP, LLC

DATE	DESCRIPTION



DATE	DESCRIPTION
12/15/2015	REVIEW SUBMITTAL

PROJECT NO: CRP CR 1024
FILE: BASE-PHASE_1
DESIGN BY: RUSSUM
DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER
EDWIN J. ROGERS
DATE: 12/15/2015
REGISTRATION NO. 50082

C-206

R:\MIRADA\PHASE 1 MASS GRADING\ENGINEERING\PHASE 1 DWG - C-206 MASS GRADING PLAN 2014121513251.PN ERIC FRANCIS




DRAINAGE LEGEND


EXISTING	PROPOSED	DESCRIPTION
x	45.0	SPOT ELEVATION
-15-	15	CONTOUR
→	→	DIRECTION OF SURFACE FLOW
□□□□□□	□□□□□□	STAKED EROSION CONTROL REPRESENTS THE SWFWMD PROJECT LIMITS AND THE LIMITS OF CLEARING AND FILLING
---	---	WETLAND LINE
---	---	25' WETLAND CONS. AREA SETBACK / LANDWARD EXTENT OF UPLAND BUFFER
---	---	100YR FLOOD LINE
○ PB-#	○ PB-#	POND BORING
---	---	PHASE 1 FILL LIMITS
---	---	MASS GRADING FLOW LINE
---	---	MASS GRADING RIDGE

EXISTING TOPOGRAPHIC SURVEY PROVIDED BY D.C. JOHNSON & ASSOCIATES, DATED 12/1/2014.

THIS PROJECT LIES IN FLOOD ZONES A, AE, & X ACCORDING TO FLOOD INSURANCE RATE MAPS FOR PASCO COUNTY, FLORIDA. FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) - FLOOD INSURANCE RATE MAP (FIRM) COMMUNITY PANEL NOS. 12101C 0258F, 12101C 0259F, 12101C 0266F, & 12101C 0267F. DATED AUGUST 28, 2008 AND ISSUED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY.



KEY MAP



HEIDT DESIGN
 Civil Engineering • Planning & GIS
 Transportation Engineering
 Ecological Services • Landscape Architecture

5806-B Breckenridge Pkwy
 Tampa, Florida 33610
 Office: 813-253-5311
 Fax: 813-464-7629
 www.HeidtDesign.com

MIRADA
 PHASE 1 MASS GRADING PLAN

MASS GRADING PLAN

PREPARED FOR: **METRO DEVELOPMENT GROUP, LLC**

DATE	DESCRIPTION
12/15/2015	REVIEW SUBMITTAL

PROJECT NO: CRP CR 1024
 FILE: BASE-PHASE_1
 DESIGN BY: RUSSUM
 DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER


EDWIN J. ROGERS
 DATE: _____
 REGISTRATION NO. 50082

C-207

R:\MIRADA\PHASE 1 MASS GRADING\ENGINEERING\PHASE 1 DWG - C-207 MASS GRADING PLAN 2014121513251.PN ERIC FRANCIS
 © COPYRIGHT 2015 HEIDT DESIGN, LLC. ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENTATION OR INFORMATION CONTAINED HEREIN MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT PERMISSION IN WRITING FROM HEIDT DESIGN, LLC. IN ADVANCE. CONSENT IS HEREBY GRANTED SPECIFICALLY TO GOVERNMENT AGENCIES TO REPRODUCE THIS DOCUMENTATION FOR OFFICIAL USE ONLY.

STRUCTURE TABLE			
STR. NO.	STR. TYPE	TOP ELEV.	COMMENTS
1	TYPE 1 CURB INLET	104.60	TEMP 4'6"X4'6" TOP W/ NEENAH R-2565-F GRATE; 6' DIA.; FUTURE 18" RCP @ INV (N) = 95.97; BRICK & MORTAR
2	MES 24" RCP		
3	TYPE D GRATE INLET	102.00	W/ALTERNATE B BOTTOM
4	MES 42" RCP		
5	TYPE D GRATE INLET	103.00	
6	MES 36" RCP		
7	TYPE D GRATE INLET	99.50	
8	MES 30" RCP		
9	TYPE C GRATE INLET	105.50	
10	MES 24" RCP		
11	TYPE D GRATE INLET	102.90	
12	MES 36" RCP		
13	TYPE D GRATE INLET	110.60	W/ALTERNATE B BOTTOM
14	MES 42" RCP		
15	TYPE C GRATE INLET	103.50	
16	MES 18" RCP		
17	TYPE C GRATE INLET	102.50	
18	MES 24" RCP		
19	TYPE D GRATE INLET	99.70	
20	MES 30" RCP		
21	TYPE D GRATE INLET	102.50	
22	MES 30" RCP		
23	TYPE 1 CURB INLET	103.23	TEMP 4'6"X4'6" TOP W/ NEENAH R-2565-F GRATE; 6' DIA.; FUTURE 18" RCP @ INV (NE) = 98.57; FUTURE 30" RCP @ INV (SE) = 93.39; BRICK & MORTAR
24	MES 36" RCP		
25	TYPE 1 CURB INLET	102.33	TEMP 4'6"X4'6" TOP W/ NEENAH R-2565-F GRATE; 6' DIA.; FUTURE 18" RCP @ INV (SW) = 97.09; BRICK & MORTAR
26	MES 24" RCP		
27	TYPE 1 CURB INLET	103.28	TEMP 4'6"X4'6" TOP W/ NEENAH R-2565-F GRATE; 6' DIA.; FUTURE 18" RCP @ INV (SW) = 97.99; BRICK & MORTAR
28	MES 24" RCP		

PIPE TABLE							
START STR.	END STR.	PIPE DIMENSION & MATERIAL	LENGTH	SLOPE	START INV.	END INV.	FALL IN FEET
1	2	24" RCP	68	0.18%	95.47	95.35	0.12
3	4	42" RCP	391	0.10%	94.00	93.60	0.40
5	6	36" RCP	368	0.08%	96.00	95.70	0.30
7	8	30" RCP	386	0.10%	92.20	91.80	0.40
9	10	24" RCP	355	0.11%	99.00	98.60	0.40
11	12	36" RCP	38	0.53%	95.50	95.30	0.20
13	14	42" RCP	69	0.29%	103.00	102.80	0.20
15	16	18" RCP	85	0.24%	99.00	98.80	0.20
17	18	24" RCP	60	0.33%	96.00	95.80	0.20
19	20	30" RCP	56	0.36%	94.00	93.80	0.20
21	22	30" RCP	46	0.43%	96.00	95.80	0.20
23	24	36" RCP	71	0.14%	92.89	92.79	0.10
25	26	24" RCP	121	0.18%	93.22	93.00	0.22
27	28	24" RCP	158	0.18%	93.28	93.00	0.28



HEIDT DESIGN
Civil Engineering • Planning & GIS
Transportation Engineering
Ecological Services • Landscape Architecture

5806-B Breckenridge Pkwy.
Tampa, Florida 33610
Office: 813-253-5311
Fax: 813-464-7629
www.HeidtDesign.com

Engineering Business Certificate of Authorization No. 28752
Landscape Architecture Certificate of Authorization No. LC2600405

MIRADA
PHASE 1 MASS GRADING PLAN
STORM STRUCTURE DATA

PREPARED FOR:
METRO DEVELOPMENT GROUP, LLC

DATE	DESCRIPTION
12/15/2015	REVIEW SUBMITTAL





PROJECT NO: CRP CR 1024
FILE: STORM
DESIGN BY: RUSSUM
DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER

EDWIN J. ROGERS
DATE: _____
REGISTRATION NO. 50082

C-208

RAMBLERWAY PHASE 1 MASS GRADING ENGINEERING STORM DWS-C-208 2014.12.15 2:51 PM ERIC FRANCIS



HEIDT DESIGN
Civil Engineering • Planning & GIS
Transportation Engineering
Ecological Services • Landscape Architecture
Engineering Business Certificate of Authorization No. LC76000405
Landscape Architecture Certificate of Authorization No. LC76000405

MIRADA
PHASE 1 MASS GRADING PLAN
FLOODPLAIN MITIGATION & POND
DETAILS
PREPARED FOR: METRO DEVELOPMENT GROUP, LLC

NO.	DATE	DESCRIPTION


NO.	DATE	REVIEW SUBMITTAL	DESCRIPTION
1	12/15/2014		

PROJECT NO: CRP CR 1024
FILE: SEC
DESIGN BY: RUSSUM
DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER
EDWIN J. ROGERS
DATE:
REGISTRATION NO. 50082

C-232

R:\MIRADA\PHASE 1 MASS GRADING\ENGINEERING\SEC DWG - C-232 2014.12.15 13:23 PM ERIC FRANCIS



N

0 300 600

GRAPHIC SCALE: 1" = 300'

LEGEND

- EXISTING WETLAND BOUNDARY
- 25' WETLAND SETBACK
- PROJECT BOUNDARY LIMITS
- BASIN LIMITS

HEIDT DESIGN
Civil Engineering • Planning & GIS
Transportation Engineering
Ecological Services • Landscape Architecture

5806-B Breckenridge Pkwy
Tampa, Florida 33610
Office: 813-253-5311
Fax: 813-464-7629
www.HeidtDesign.com

Engineering Business Certificate of Authorization No. 28792
Landscape Architecture Certificate of Authorization No. LC26000405

MIRADA
PHASE I MASS GRADING PLAN
PRE-DEVELOPMENT BASIN MAP

PREPARED FOR: METRO DEVELOPMENT GROUP, LLC

DATE	DESCRIPTION
12/15/2015	REVIEW SUBMITTAL

PROJECT NO: CRP CR 1024
FILE: DA-PRE
DESIGN BY: RUSSUM
DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER

EDWIN J. ROGERS
DATE:
REGISTRATION NO. 50082

C-900

NOTE: NO CONSTRUCTION ACTIVITY SHALL TAKE PLACE WITHIN 50 FEET OF WELL LOCATIONS SHOWN ON THESE PLANS UNTIL THE WELL HAS BEEN PROPERLY ABANDONED IN ACCORDANCE WITH SOUTHWEST FLORIDA WATER MANAGEMENT DISTRICT REGULATIONS BY A CERTIFIED WELL CONTRACTOR

ELEVATIONS BASED ON:
NORTH AMERICAN VERTICAL DATUM
CONVERSION:
NAVD 88 TO NGVD 29 = +0.85

R:\MIRADA\PHASE I MASS GRADING\ENGINEERING\DA-PRE DWG - C-900 2014121513254.PN ERIC FRANCIS

STORM WATER POLLUTION PREVENTION PLAN

Contained on these plans and within the following notes is a storm water pollution prevention plan (swppp) which has been developed by Heidt Design, LLC in accordance with the Florida Department of Environmental Protection's (FDEP) "National Pollutant Discharge Elimination System" (NPDES) generic permit for stormwater discharge from large and small construction activities.

The following entities are identified as team members of "SWPPP": Heidt Design, LLC, the developer as identified in the title box of these plans, and the site contractor and his sub-contractors. Each team member has specific responsibilities and obligations. In general, all team members, with regard to their involvement and responsibilities on the project, are to implement all necessary storm water management controls to assure compliance with the NPDES generic permit for storm water discharges from construction activities, the Southwest Florida Water Management District Permit, the applicable local governing agency (i.e. Pasco County) and the guidelines listed in the SWPPP. The duties and responsibilities of the team members as they pertain to the SWPPP are as follows:

HEIDT DESIGN, LLC:

- A. Develop SWPPP including, but not limited to, retention/detention ponds, control structures, erosion control methods and locations and stabilization criteria. This design is included within these construction plans and the following notes and instructions.
B. Submit and obtain the necessary design related storm water permits from the Florida Department of Environmental Protection, the Southwest Florida Water Management District and other applicable governmental bodies.
C. Upon notification by the developer of his intent to commence construction, submit a notice of intent to the FDEP on behalf of the developer and copy the contractor including SWPPP certification and copy of the permit.
D. Submit to SWFWMD and the operator of the municipal separate storm water system, if applicable, a letter of construction commencement.
E. Complete and submit a notice of termination and certification for developer. The NOT's shall be submitted no more than 30 days after:
(a) Completion of the project and final stabilization of the site or
(b) When responsibility for the site has ended. Final stabilization as defined by EPA is when all soil disturbing activities at the site have been completed and a uniform, without large bare areas) perennial vegetative cover with a density of 70% of the native background vegetative cover for the area has been established on all upland areas and areas not covered by permanent structures. As an alternative, equivalent permanent stabilization measures (such as riprap, gabions, or geotextiles) may be employed. The client shall notify Heidt Design, LLC when one of these criteria has been met.

CONTRACTOR:

- A. Sign and return to Heidt a contractor's certification form certifying your understanding of and willingness to comply with the Storm Water Pollution Prevention Plan no later than 48 hours prior to commencement of construction. Also, each subcontractor affected by the SWPPP must certify to the contractor that they understand and shall comply with the NPDES Permit and SWPPP. A record of these certifications shall be maintained by the contractor on site.
B. During construction, assure compliance with the designed Storm Water Pollution Prevention plans prepared by Heidt Design, LLC and the NPDES Generic Permit for storm water discharges from large and small construction activities.
C. Maintain a copy of the construction plans, which include the Storm Water Pollution Prevention Plan, the NOI, and all inspection reports and certifications on site.
D. Undertake all reasonable Best Management Practices (BMP's) to assure that silted or otherwise polluted storm water is not allowed to discharge from the site during all phases of construction. Stabilization BMP's that may be used include:
Temporary or permanent seeding, mulching, geotextiles, sodding, vegetative buffer strips, protection of trees and preservation of mature vegetation. Structural erosion and sediment control BMP's that may be used include: straw bale dikes, silt fences, earth dikes, brush barriers, drainage swales, check dams, subsurface drain, pipe slope drain, level spreaders, storm drain inlet protection, outlet protection, sediment traps, and temporary sediment basins. Detention ponds may also be used as temporary sediment basins. Additional BMP's that may need to be implemented include: providing protected storage areas for chemicals, paints, solvents, fertilizers, and other potentially toxic materials. Providing waste receptacles at convenient locations and providing regular collection of wastes, including building material wastes. Minimizing off-site tracking of sediments. Making adequate preparations, including training and equipment to contain spills of oil and hazardous materials. Complying with applicable state or local waste disposal, sanitary sewer or septic system regulations and the use of appropriate pollution prevention measures for allowable non-storm water components of discharge.
E. Notify Heidt Design, LLC and the developer in writing of any non-storm water pollution sources which are being stored, or otherwise used during the construction of the project, i.e., fertilizers, fuels, pesticides, other chemicals. This notification should be accompanied with the contractor's design and methods to prevent pollution run-off from these sources.
F. Develop a maintenance and inspection plan which includes, but is not limited to the following:
(a) The specific areas to be inspected and maintained that includes all the disturbed areas and material storage areas of the site.
(b) The erosion and sediment controls identified in the swppp to be maintained and inspected and those additional controls that the contractor deems necessary.
(c) Maintenance procedures.
(d) The procedure to follow if additional work is required or whom to call.
(e) Inspections and maintenance forms.
(f) The personnel assigned to each task.
The following shall be inspected a minimum of once a week or within 24 hours after 0.50 inches of rainfall:
Stabilization measures (once a month if fully stabilized).
Structural controls.
Discharge points.
Construction entrances and exits.
Areas used for storage of exposed materials.
An inspection form shall be completed for each inspection. Any permit violations should be noted and corrective measures shall be taken no later than 7 days after the inspection occurred. If revisions to the SWPPP are needed, a report form for changes in the SWPPP shall be completed and a copy sent to Heidt Design, LLC the original shall be kept on-site as documentation of the change. If the inspection passes, a certification that the facility is in compliance with the SWPPP and the NPDES Permit must be signed by a duly authorized representative of the principal executive official of the operator of the SWPPP with one of the following qualifications:

- 1. Has successfully completed the Florida Stormwater, Erosion and Sediment Control Inspector Training Program.
2. Successfully completed a similar training program.
3. Has enough practical on the job training to be qualified to perform the inspections.
4. Retain inspection reports and certifications for at least three years.
G. Site stabilization measures shall be initiated as soon as practical but in no case more than 7 days, in portions of the site where construction activities have temporarily or permanently ceased.
H. Releases in excess of reportable quantities.
1. The discharge of hazardous substances or oil in the stormwater discharge(s) from a facility or activity shall be prevented or minimized in accordance with the applicable Stormwater Pollution Prevention Plan for the facility or activity. This permit does not relieve the operator of the reporting requirements of 40 cfr part 117 and 40 cfr part 302. Where a release containing a hazardous substance in an amount equal to or in excess of a reporting quantity established under either 40 cfr 117 or 40 cfr 302, occurs during a 24 hour period.
A. The operator is required to notify the State Warning Point (800-210-0519 or 850-413-9911) as soon as he or she has knowledge of the discharge.
B. The operator shall submit within 14 calendar days of knowledge of the release a written description of the release (including the type and estimate of the amount of material released), the date that such release occurred, the circumstances leading to the release, and remedial steps to be taken, to the Florida Department of Environmental Protection, NPDES Stormwater Section, Mail Station 2500, 2600 Blair Stone Road, Tallahassee, Florida 32399-2400; and
C. The Stormwater Pollution Prevention Plan required under part V of this permit must be modified within 14 calendar days of knowledge of the release to provide a description of the release, the circumstances leading to the release, and the date of the release. In addition, the plan must be reviewed to identify measures to prevent the recurrence of such releases and to respond to such releases, and the plan must be modified where appropriate.
2. This permit does not authorize the discharge of hazardous substances or oil resulting from an on-site spill.

DEVELOPER:

- A. Notify Heidt of your intent to commence construction. Sign the Notice of Intent form as operator of the storm water discharge facility and permittee and return to Heidt Design, LLC.
B. Sign a certification of Storm Water Pollution Prevention Plan and return to Heidt Design, LLC.
C. Notify Heidt when it is time to submit a Notice of Termination as defined under part E of the Heidt Design, LLC section of the SWPPP. Sign and return to Heidt Design, LLC for submittal to FDEP a Notice of Termination form and certification.

PRE-DEVELOPED SITE INFORMATION:

- 1. Total Site Acreage: **398.7± AC.**
2. Land Use: **UNDEVELOPED - AGRICULTURAL**
3. Vegetation: **PRIMARILY BAHIA AND OTHER GRASSES GROWN FOR SEED**
4. Receiving waters or municipal separate storm water system: **BAYOU BRANCH**
5. 2 Year/24 Hour Rainfall Depth: **5.0"**
6. Soil Types: **SPARR, HEWNAW, AND BASSINGER FINE SANDS**

PROJECT INFORMATION:

- 1. Project Type - **RESIDENTIAL/MASS GRADING**
2. Anticipated Construction Sequence is as follows:
1. Complete Erosion Control Installation
2. Clearing and Grubbing
3. Earthwork Activities
4. Storm Water System Construction

The BMP's listed in part D of the Contractor Section of the SWPPP shall be considered during all phases of construction.

- 3. Anticipated Start Date: **02/20/15**
4. Anticipated Completion Date: **06/20/15**
5. Total Acres Disturbed: **236.31**
6. Pre-Developed "C" Factor: **0.20**
7. Post-Developed "C" Factor: **0.25**
8. The Storm Water Management System, upon completion of construction and appropriate certification and as-built submittals will be operated and maintained by **MIRADA CDD**
9. The potential source of pollution from this project is on-site development and construction activity.

OWNER'S INSTRUCTIONS FOR MAINTENANCE AND INSPECTION OF STORMWATER FILTER FACILITIES

Drainage systems should be inspected on a routine basis to ensure that they are functioning properly. Inspections can be on an annual or semi-annual basis, but should always be conducted following major storms. Systems that incorporate infiltration are most critical since poor maintenance practices can soon render them inefficient. Visual inspections of sand filters, control structures, and outfall pipes are highly recommended. It should be stressed that good records should be kept on all maintenance operations to help plan future work and identify facilities requiring attention.

Sand filter surfaces are sometimes scarified or break up silt deposits and restore porosity. This should be accomplished after all sediment has been removed from the surface. After removing large debris (cups, paper, wood, etc.) it is recommended that raking the top 3" will properly scarify the surface or it may be required to replace the sand. Another technique requires removing the sand for washing.

The filter system is designed to have a wet-dry cycle to inhibit algae or bacterial growth. Cleanout frequency of filter beds will depend on whether they are vegetated or non-vegetated and will be a function of their storage capacity, infiltration characteristics, volume of inflow, and sediment load. Filter beds should be inspected closely at least once a year.

Perforated underdrain pipes are located 2' below the sand and cleanouts are located at the end of the system. In the event of sediment build-up in the underdrain pipe, cleaning can be accomplished through the cleanout with several of the techniques outlined below.

Methods and equipment for cleanout of systems various types of equipment are available commercially for maintenance of drainage systems. The most frequently used equipment and techniques are listed below.

- 1. Vacuum Pump
This device is normally used to remove sediment from sumps and pipes. The equipment for this system is generally mounted on a vehicle. It requires a 200 - 300 gallon (0.757 - 1.36m) holding tank and a vacuum pump that has a 10" (254mm) diameter flexible hose with a serrated metal end for breaking up cake sediment. A two-man crew can clean a catch basin in 5 to 10 minutes. This system can remove stones, bricks, leaves, litter and sediment deposits. Normal working depth is 0' - 20' (0 to 6m).
2. Water Jet Spray
This equipment is generally mounted on a self-contained vehicle with a high pressure pump and a 200 - 300 gallons (0.760 to 1.144m) water supply. A 3" (76mm) flexible hose line with a metal nozzle that directs jets of water at a reverse angle, which propels the nozzle forward while blasting debris backwards toward the catch basin. As the hose line is reeled in, the jetting action forces all debris to the catch basin where it is removed by the vacuum pump equipment. Normal length of hose is approximately 200' (61m). Because of the energy supplied by the water jet, it should not be used to clean erodible trench walls.

GENERAL EROSION AND TURBIDITY CONTROL NOTES

- 1. The Site Subcontractor shall be responsible for installation and maintenance of all erosion and turbidity controls and the quality and quantity of offsite or wetland discharges.
2. Prior to construction, the Site Subcontractor is responsible for having his dewatering plan and turbidity control plan approved by the applicable reviewing agencies. Refer to the project's permit approvals and permit conditions for agencies requiring such review and approval. Questions concerning appropriate techniques should be addressed to those agencies and/or discussed with the project engineer and owner.
3. The appropriate turbidity and erosion control methodologies selected by the Site Subcontractor for this project should be made following assessment of the plans and project site specific factors and after consultations as needed with the project engineer and appropriate agencies. The Site Subcontractor will be responsible for obtaining any and all necessary permits for such activity; several factors to consider are listed below:
A. Clay content in excavated materials and/or permeabilities rates
B. Depth of cut in ponds, trenches, or utility lines
C. Ambient ground water levels
D. Actual rainfall amounts and time of year relative to normal rainy season
E. Proximity to wetlands, water bodies or offsite properties
F. "Class" designation of receiving water bodies (i.e., Outstanding Florida Waters, shellfish harvesting areas, etc.)
G. Density, type, and proximity of upland vegetation to be retained during construction (for use as possible filtration areas)
H. Fill height relative to natural grade and length and steepness of the proposed slopes
I. Existing topography and directions of surface flow
J. Type of equipment used
K. Project type
L. Duration of construction activities
M. Separation distance of onsite ponds
N. Ambient quality of surface and groundwater
O. Temporary stockpile locations and heights
4. At the onset of construction, the Site Subcontractor, as the party responsible for implementation of the erosion and sediment control plan, shall assess the above described conditions and factors with respect to relative cost effectiveness and select the appropriate methods of protection. A fairly extensive list of techniques are presented below but it must be stressed that any or all of the following may be necessary to maintain water quality and quantity standards. The construction sequencing should be thought out in advance of initiation to provide adequate protection of water quality.
5. Discharges which exceed 29 N.T.U.'s over the background levels are in violation of state water quality standards. Discharges of water quantities which affect offsite properties or may damage wetlands are also prohibited by regulating agencies.
6. The erosion and turbidity control measures shown hereon are the minimum required for agency approval. Additional control and measures may be required due to the Site Subcontractor's construction sequence & unforeseen weather conditions. Any additional measures deemed necessary by the Site Subcontractor shall be included in the lump sum bid with no extras for materials and labor allowed.
7. Hay bales or silt screens shall be installed prior to land clearing to protect water quality and to identify areas to be protected from clearing activities and maintained for the duration of the project until all soil is stabilized.
8. Floating turbidity barriers shall be in place in flowing systems or in open water lake edges prior to initiation of earthwork and maintained for the duration of the project until all soil is stabilized.
9. No clay material shall be left exposed in any stormwater storage facility. If clay or sandy-clays are encountered during stormwater storage excavation, the Site Subcontractor shall notify the Engineer immediately before proceeding with further excavation. If the Engineer of Record has determined that such soils are non-confining and must be excavated to meet permit and design conditions, excavation may proceed after obtaining written authorization from the appropriate governing agency. If said soils are left exposed at the permitted and designed depth, the Site Subcontractor shall over-excavate the pond's bottom and side slopes by a minimum of twelve (12") inches and backfill with clean sands to help prevent suspension of fine particles in the water column.
10. The installation of temporary erosion control barriers shall be coordinated with the construction of the permanent erosion control features to the extent necessary to assure effective and continuous control of erosion and water pollution throughout the life of the construction phase.
11. The type of erosion control barriers used shall be governed by the nature of the construction operation and soil type that will be exposed. Silty and clayey material may require solid sediment barriers to prevent turbid water discharge, while sandy material may need only silt screens or hay bales to prevent erosion. Floating turbidity curtains should generally be used in open water situations. Diversion ditches or swales may be required to prevent turbid stormwater runoff from being discharged to wetlands or other water bodies. It may be necessary to employ a combination of barriers, ditches, and other erosion/turbidity control measures if conditions warrant.
12. Where pumps are to be used to remove turbid waters from construction areas, the water shall be treated prior to discharge to the wetlands. Treatment methods include, for example, turbid water being pumped into grassed swales or appropriate upland vegetated areas (other than upland preservation areas and wetland buffers), sediment basins, or confined by an appropriate enclosure such as turbidity barriers or low berms, and kept confined until turbidity levels meet State Water Quality Standards.
13. The Permittee shall schedule his operations such that the area of unprotected erodible earth exposed at any one time is not larger than the minimum area necessary for efficient construction operation, and the duration of exposed, uncompleted construction to the elements shall be as short as practicable. Clearing and grubbing shall be so scheduled and performed such that grading operations can follow immediately thereafter. Grading operations shall be so scheduled and performed that permanent erosion control features can follow immediately thereafter if conditions on the project permit.
14. Water derived from various dewatering methods should be passed through sufficiently wide areas of existing upland vegetation to filter out excess turbidity. If this is not sufficient, the water shall be retained in previously constructed permanent stormwater ponds or else retained in temporary sedimentation basins until the clarity is suitable to allow for its discharge. Plugging the outfalls from completed stormwater ponds may be needed to avoid discharge. However, such situations should be monitored closely to preclude berm failure if water levels rise too high.
15. Water can be transported around the site by the use of internal swales or by pumps and pipes.
16. Sheet flow of newly filled or scraped areas may be controlled or contained by the use of brush barriers, diversion swales, interceptor ditches or low berms. Flow should be directed toward areas where sediments can sufficiently settle out.
17. Exposed soils shall be stabilized as soon as possible, especially slopes leading to wetlands. Stabilization methods include solid soil, seeding and mulching or hydromulching to provide a temporary or permanent grass cover mulch blankets, filter fabrics, etc., can be employed to provide vegetative cover.
18. Energy dissipaters (such as rip rap, a gravel bed, hay bales, etc.) shall be installed at the discharge point of pipes or swales if scouring is observed.
19. Attempt to install roadway curb and gutters as soon as possible to reduce the surface area for erosion to occur.
20. Implement storm drain inlet protection (hay bales or gravel) to limit sedimentation within the stormwater system. Perform inspections and periodic cleaning of sediments which wash out into the streets until all soil is stabilized.
21. Water discharge velocities from impounded areas and temporary sedimentation basins shall be restricted to avoid scouring in receiving areas.
22. If water clarity does not reduce to state standards rapidly enough in holding ponds, it may be possible to use chemical agents such as alum to flocculate or coagulate the sediment particles.
23. Hay bales, silt screens, or gravel beds can be added around the pipe or swale discharge points to help clarify discharges. Spreader swales may help dissipate cloudy water prior to contact with wetlands.
24. All fuel storage areas or other hazardous storage areas shall conform to accepted state or federal criteria for such containment areas.
25. Vehicle or equipment washdown areas will be sufficiently removed from wetlands or offsite areas.
26. Fugitive dust controls (primarily by using water spray trucks) shall be employed as needed to control windborn emissions.
27. If the above controls remain ineffective in precluding release of turbid water, especially during pond or utility line dewatering, then the contractor may be compelled to use a vertical dewatering system such as well points or sock drains to withdraw groundwater which may already be clear enough to allow for direct discharge to wetlands.
28. Ongoing inspections and periodic maintenance by the Site Subcontractor shall occur throughout construction as necessary to insure the above methods are working suitably. This may be needed daily, if conditions so warrant. Site Subcontractors are encouraged to obtain and thoroughly review The Florida Development Manual: A Guide to Sound Land and Water Management, which was developed by the State of Florida Department of Environmental Protection in 1988. This provides fairly in-depth discussions of recommended techniques and also provides specific design and technical standards. A copy of this document is available for review at Heidt Design, LLC.
29. The contractor will perform daily inspections of all on-site wetlands within the construction area to ensure that water levels within those wetlands are not excessively impounded prior to the time when the permitted control structure or outfall is built. Water levels significantly above normal should be corrected at a frequency that prevents a change in the vegetative character or health of any wetlands.





POND/LAKE EXCAVATION NOTE:

No excavation shall extend below the permitted design depths/elevations shown on the drawings, unless additional testing supports otherwise; and no lower semi-confining unit clayey soil material and/or no limestone materials shall be excavated, regardless if these materials are encountered within the permitted excavation depths/elevations. If any lower semi-confining unit clayey soil materials or limestone materials are encountered above the permitted depths/elevations, then excavation operations shall cease in the general area and the Engineer of Record shall be notified immediately.

WETLANDS NOTE:


There are no wetland impacts proposed and therefore, no mitigation required.
Conservation Area designation is given to all protected wetlands per Pasco County requirements. They are not designated as "Conservation Easements" for SWFWMD compensation.

DRAINAGE LEGEND



EROSION CONTROL DETAILS

NOTE: THE EROSION BARRIERS AS SHOWN ARE NOT TO BE CONFINED TO MEAN THAT THEY ARE ALL THAT MAY BE REQUIRED. THE CONTRACTOR IS TO TAKE WATER MEASURES NECESSARY TO CONTROL EROSION THROUGHOUT THE PROJECT.



* MUST EXTEND FULL WIDTH OF INGRESS END EGRESS OPERATION

SOIL TRACKING EROSION CONTROL TYPICAL CONSTRUCTION ENTRANCE

NOT TO SCALE

HEIDT DESIGN logo and contact information: 5806-B Breckenridge Pkwy, Tampa, Florida 33610, Office: 813-253-5311, Fax: 813-664-7629, www.HeidtDesign.com

MIRADA PHASE 1 MASS GRADING PLAN CSWMP METRO DEVELOPMENT GROUP, LLC PREPARED FOR: DATE: DESCRIPTION: REVIEW SUBMITTAL: DATE: DESCRIPTION: 1 12/15/2015

Table with columns for REVIEW SUBMITTAL, DATE, and DESCRIPTION. Row 1: 1, 12/15/2015, [blank]



PROJECT NO: CRP CR 1024
FILE: CSWMP
DESIGN BY: RUSSUM
DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER

EDWIN J. ROGERS
DATE:
REGISTRATION NO. 50082


C-902

VERTICAL SCALE: 1"=10' HORIZONTAL SCALE: 1"=40' DATE: 12/15/2015 TIME: 2:35 PM ERIC FRANCIS



- LEGEND**
- EXISTING WETLAND BOUNDARY
 - PROJECT BOUNDARY LIMITS
 - PHASE 1 BOUNDARY LIMITS
 - PROPOSED POND LIMITS
 - ▨ 100YR FLOOD PLAIN LIMITS
 - PROPOSED POND LIMITS
 - SILT FENCE
 - CONSTRUCTION ACCESS
 - FILL LIMITS
 - 12" I TREE TO REMAIN
 - × 14" I TREE TO BE REMOVED

- EXISTING TREE CODES**
- AP AUSTRALIAN PINE
 - C CYPRESS
 - CL CHERRY LAUREL
 - CM CAMPHOR
 - CO COCONUT PALM
 - CP CABBAGE PALM/SABAL PALM
 - EL ELM
 - F FIG (STRANGLER FIG)
 - FW FIDDLEWOOD
 - H HICKORY
 - LA LAUREL (DIAMOND OAK)
 - LB LOBLOLLY BAY
 - LI LIVE OAK
 - M MAGNOLIA
 - MB MARLBERRY
 - MG SOUTHERN MAGNOLIA
 - MH MAHOGANY
 - MY MYRTLE OAK
 - NP NORFOLK PINE
 - P LONELEAF PINE
 - PC PECAN
 - PE PERSIMMON
 - PM ROYAL PALM
 - PT PAPER TREE
 - QP QUEEN PALM
 - RB RED BAY
 - RM RED MAPLE
 - SB SWEET BAY MAGNOLIA
 - SC SYCAMORE
 - SG SWEET GUM
 - SL SLASH (YELLOW PINE)
 - SP SAND PINE (SCRUB PINE)
 - T TALLOW WOOD
 - TO TURKEY OAK
 - WO WATER OAK
 - WP WASHINGTON PALM
 - WX WAX MYRTLE



HEIDT DESIGN
 Civil Engineering • Planning & GIS
 Transportation Engineering
 Ecological Services • Landscape Architecture
 Engineering Business Certificate of Authorization No. LC26000405
 Landscape Architecture Certificate of Authorization No. LC26000405

5806-B Breckenridge Pkwy.
 Tampa, Florida 33610
 Office: 813-255-5311
 Fax: 813-464-7629
 www.HeidtDesign.com

MIRADA
PHASE 1 MASS GRADING PLAN
TREE REMOVAL & REPLACEMENT PLAN

PREPARED FOR: METRO DEVELOPMENT GROUP, LLC

NO.	DATE	DESCRIPTION

NO.	DATE	DESCRIPTION
1	12/15/2015	REVIEW SUBMITTAL


PROJECT NO: CRP CR 1024
 FILE: L-101-MG
 DESIGN BY: RUSSUM
 DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER

DOUG DIERLICH
 DATE: _____
 REGISTRATION NO. 0001696

L-101

R:\MIRADAPHASE 1\MASS GRADING\ENGINEERING\L-101-MG.DWG L-101 2014/12/13 2:56 PM ERIC FRANCIS




N

0 50 100
GRAPHIC SCALE: 1" = 50'
LEGEND

- EXISTING WETLAND BOUNDARY
- PROJECT BOUNDARY LIMITS
- - - PHASE 1 BOUNDARY LIMITS
- - - PROPOSED POND LIMITS
- /// 100YR FLOOD PLAIN LIMITS
- - - PROPOSED POND LIMITS
- o o o o o o o o o o SILT FENCE
- - - CONSTRUCTION ACCESS
- FILL LIMITS
- o 12L TREE TO REMAIN
- X 14L TREE TO BE REMOVED

EXISTING TREE CODES

AP	AUSTRALIAN PINE
C	CYPRESS
CL	CHERRY LAUREL
CM	CAMPHOR
CO	COCONUT PALM
CP	CABBAGE PALM/SABAL PALM
EL	ELM
F	FIG (STRANGLER FIG)
FW	FIDDLEWOOD
H	HICKORY
LA	LAUREL (DIAMOND OAK)
LB	LOBLOLLY BAY
LI	LIVE OAK
M	MAGNOLIA
MB	MARLBERRY
MG	SOUTHERN MAGNOLIA
MH	MAHOGANY
MY	MYRTLE OAK
NP	NORFOLK PINE
P	LONELEAF PINE
PC	PECAN
PE	PERSIMMON
PM	ROYAL PALM
PT	PAPER TREE
QP	QUEEN PALM
RB	RED BAY
RM	RED MAPLE
SB	SWEET BAY MAGNOLIA
SC	SYCAMORE
SG	SWEET GUM
SL	SLASH (YELLOW PINE)
SP	SAND PINE (SCRUB PINE)
T	TALLOW WOOD
TO	TURKEY OAK
WO	WATER OAK
WP	WASHINGTON PALM
WX	WAX MYRTLE



HEIDT DESIGN
Civil Engineering • Planning & GIS
Transportation Engineering
Ecological Services • Landscape Architecture

5806-B Breckenridge Pkwy.
Tampa, Florida 33610
Office: 813-253-5311
Fax: 813-464-7629
www.HeidtDesign.com

Engineering Business Certificate of Authorization No. 28792
Landscape Architecture Certificate of Authorization No. LC26000405

MIRADA
PHASE 1 MASS GRADING PLAN
TREE REMOVAL & REPLACEMENT PLAN

PREPARED FOR: METRO DEVELOPMENT GROUP, LLC

NO.	REVIEW SUBMITTAL	DATE	DESCRIPTION
1	12/15/2015		



NO.	REVIEW SUBMITTAL	DATE	DESCRIPTION
1	12/15/2015		

PROJECT NO: CRP CR 1024
FILE: L-101-MG
DESIGN BY: RUSSUM
DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER
DOUG DIERLICH
DATE: _____
REGISTRATION NO. 0001696


L-102

R:\MIRADA\PHASE 1\MSS GRADING\ENGINEERING\L-101-MG.DWG L-102 2014/12/13 2:56 PM ERIC FRANCIS



- LEGEND**
- EXISTING WETLAND BOUNDARY
 - PROJECT BOUNDARY LIMITS
 - PHASE 1 BOUNDARY LIMITS
 - PROPOSED POND LIMITS
 - 100YR FLOOD PLAIN LIMITS
 - PROPOSED POND LIMITS
 - SILT FENCE
 - CONSTRUCTION ACCESS
 - FILL LIMITS
 - 12"LI TREE TO REMAIN
 - ✕ 14"LI TREE TO BE REMOVED

- EXISTING TREE CODES**
- AP AUSTRALIAN PINE
 - C CYPRESS
 - CL CHERRY LAUREL
 - CM CAMPHOR
 - CO COCONUT PALM
 - CP CABBAGE PALM/SABAL PALM
 - EL ELM
 - F FIG (STRANGLER FIG)
 - FW FIDDLEWOOD
 - H HICKORY
 - LA LAUREL (DIAMOND OAK)
 - LB LOBLOLLY BAY
 - LI LIVE OAK
 - M MAGNOLIA
 - MB MARLBERRY
 - MG SOUTHERN MAGNOLIA
 - MH MAHOGANY
 - MY MYRTLE OAK
 - NP NORFOLK PINE
 - P LONELEAF PINE
 - PC PECAN
 - PE PERSIMMON
 - PM ROYAL PALM
 - PT PAPER TREE
 - QP QUEEN PALM
 - RB RED BAY
 - RM RED MAPLE
 - SB SWEET BAY MAGNOLIA
 - SC SYCAMORE
 - SG SWEET GUM
 - SL SLASH (YELLOW PINE)
 - SP SAND PINE (SCRUB PINE)
 - T TALLOW WOOD
 - TO TURKEY OAK
 - WO WATER OAK
 - WP WASHINGTON PALM
 - WX WAX MYRTLE



HEIDT DESIGN
 Civil Engineering • Planning & GIS
 Transportation Engineering
 Ecological Services • Landscape Architecture
 Engineering Business Certificate of Authorization No. 28792
 Landscape Architecture Certificate of Authorization No. LC26000405

5806-B Breckenridge Pkwy.
 Tampa, Florida 33610
 Office: 813-255-5311
 Fax: 813-464-7629
 www.HeidtDesign.com

MIRADA
PHASE 1 MASS GRADING PLAN
TREE REMOVAL & REPLACEMENT PLAN

PREPARED FOR: METRO DEVELOPMENT GROUP, LLC

NO.	DATE	DESCRIPTION



NO.	DATE	REVIEW SUBMITTAL	DESCRIPTION
1	12/15/2015		

PROJECT NO: CRP CR 1024
 FILE: L-101-MG
 DESIGN BY: RUSSUM
 DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER
DOUG DIERLICH
 DATE: _____
 REGISTRATION NO. 0001696

L-103


R:\MIRADAPHASE 1\MSS GRADING\ENGINEERING\L-101-MG.DWG L-103 2014/12/13 2:56 PM ERIC FRANCIS



- LEGEND**
- EXISTING WETLAND BOUNDARY
 - PROJECT BOUNDARY LIMITS
 - PHASE 1 BOUNDARY LIMITS
 - PROPOSED POND LIMITS
 - 100YR FLOOD PLAIN LIMITS
 - PROPOSED POND LIMITS
 - SILT FENCE
 - CONSTRUCTION ACCESS
 - FILL LIMITS
 - 12" TREE TO REMAIN
 - × 14" TREE TO BE REMOVED

- EXISTING TREE CODES**
- AP AUSTRALIAN PINE
 - C CYPRESS
 - CL CHERRY LAUREL
 - CM CAMPHOR
 - CO COCONUT PALM
 - CP CABBAGE PALM/SABAL PALM
 - EL ELM
 - F FIG (STRANGLER FIG)
 - FW FIDDLEWOOD
 - H HICKORY
 - LA LAUREL (DIAMOND OAK)
 - LB LOBLOLLY BAY
 - LI LIVE OAK
 - M MAGNOLIA
 - MB MARLBERRY
 - MG SOUTHERN MAGNOLIA
 - MH MAHOGANY
 - MY MYRTLE OAK
 - NP NORFOLK PINE
 - P LONELEAF PINE
 - PC PECAN
 - PE PERSIMMON
 - PM ROYAL PALM
 - PT PAPER TREE
 - QP QUEEN PALM
 - RB RED BAY
 - RM RED MAPLE
 - SB SWEET BAY MAGNOLIA
 - SC SYCAMORE
 - SG SWEET GUM
 - SL SLASH (YELLOW PINE)
 - SP SAND PINE (SCRUB PINE)
 - T TALLOW WOOD
 - TO TURKEY OAK
 - WO WATER OAK
 - WP WASHINGTON PALM
 - WX WAX MYRTLE

KEY MAP



HEIDT DESIGN
 Civil Engineering • Planning & GIS
 Transportation Engineering
 Ecological Services • Landscape Architecture
 Engineering Business Certificate of Authorization No. 28792
 Landscape Architecture Certificate of Authorization No. LC26000405

5806-B Breckenridge Pkwy
 Tampa, Florida 33610
 Office: 813-253-5311
 Fax: 813-464-7629
 www.HeidtDesign.com

MIRADA
PHASE 1 MASS GRADING PLAN
TREE REMOVAL & REPLACEMENT PLAN

PREPARED FOR: METRO DEVELOPMENT GROUP, LLC



NO.	DATE	DESCRIPTION
1	12/15/2015	REVIEW SUBMITTAL

PROJECT NO: CRP CR 1024
 FILE: L-101-MG
 DESIGN BY: RUSSUM
 DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER
DOUG DIERLICH
 DATE: _____
 REGISTRATION NO. 0001696

L-104


R:\MIRADA\PHASE 1\MSS GRADING\ENGINEERING\L-101-MG.DWG L-104 2014/12/13 2:56 PM ERIC FRANCIS



- LEGEND**
- EXISTING WETLAND BOUNDARY
 - PROJECT BOUNDARY LIMITS
 - PHASE 1 BOUNDARY LIMITS
 - PROPOSED POND LIMITS
 - ▨ 100YR FLOOD PLAIN LIMITS
 - PROPOSED POND LIMITS
 - SILT FENCE
 - CONSTRUCTION ACCESS
 - █ FILL LIMITS
 - 12"LI TREE TO REMAIN
 - ✕ 14"LI TREE TO BE REMOVED

- EXISTING TREE CODES**
- AP AUSTRALIAN PINE
 - C CYPRESS
 - CL CHERRY LAUREL
 - CM CAMPHOR
 - CO COCONUT PALM
 - CP CABBAGE PALM/SABAL PALM
 - EL ELM
 - F FIG (STRANGLER FIG)
 - FW FIDDLEWOOD
 - H HICKORY
 - LA LAUREL (DIAMOND OAK)
 - LB LOBLOLLY BAY
 - LI LIVE OAK
 - M MAGNOLIA
 - MB MARLBERRY
 - MG SOUTHERN MAGNOLIA
 - MH MAHOGANY
 - MY MYRTLE OAK
 - NP NORFOLK PINE
 - P LONELEAF PINE
 - PC PECAN
 - PE PERSIMMON
 - PM ROYAL PALM
 - PT PAPER TREE
 - QP QUEEN PALM
 - RB RED BAY
 - RM RED MAPLE
 - SB SWEET BAY MAGNOLIA
 - SC SYCAMORE
 - SG SWEET GUM
 - SL SLASH (YELLOW PINE)
 - SP SAND PINE (SCRUB PINE)
 - T TALLOW WOOD
 - TO TURKEY OAK
 - WO WATER OAK
 - WP WASHINGTON PALM
 - WX WAX MYRTLE

KEY MAP



HEIDT DESIGN
 Civil Engineering • Planning & GIS
 Transportation Engineering
 Ecological Services • Landscape Architecture
 Engineering Business Certificate of Authorization No. 28792
 Landscape Architecture Certificate of Authorization No. LC26060405

5806-B Breckenridge Pkwy.
 Tampa, Florida 33610
 Office: 813-253-5311
 Fax: 813-464-7629
 www.HeidtDesign.com

MIRADA
PHASE 1 MASS GRADING PLAN
TREE REMOVAL & REPLACEMENT PLAN

PREPARED FOR: METRO DEVELOPMENT GROUP, LLC

NO.	DATE	DESCRIPTION
1	12/15/2015	REVIEW SUBMITTAL

PROJECT NO: CRP CR 1024
 FILE: L-101-MG
 DESIGN BY: RUSSUM
 DRAWN BY: FRANCIS

FLORIDA PROFESSIONAL ENGINEER
 DOUG DIERLICH
 DATE: _____
 REGISTRATION NO. 0001696

L-106

R:\MIRADA\PHASE 1\MSS GRADING\ENGINEERING\L-101-MG.DWG L-106 2014/12/13 2:56 PM ERIC FRANCIS

